

16-28-16W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- EL DORADO REFINING COMPANY
Farm- Kinney "B" No. 1

SEC. 16 T. 28 R.16W
SE SW NE

Total Depth. 4825'
Comm. 9-24-57 Comp. 10-9-57
Shot or Treated.
Contractor. Prime Drilling Company
Issued. 2-15-58

County Kiowa
KANSAS



CASING:
8 5/8" 363' cem w/250 sx
5 1/2" 4812' cem w/125 sx

Elevation. 2161 RB

Production. 40 BOPD

Figures indicate Bottom of Formations.

shale	70
sand	195
shale & shells	363
red bed & shale	460
red bed, shale & shells	1070
Anhydrite	1112
shale, red bed & shells	1600
shale & shells	2175
shale & lime	2250
lime	2550
lime & shale	2655
lime	2730
lime & shale	2840
lime	2930
lime & shale	3780
lime	3985
lime & shale	4140
lime	4638
shale & lime	4695
lime	4735
Mississippi	4825-RTD
Total Depth	

SAMPLE TOPS:	
Heebner	4023
Toronto	4045
Douglas	4066
Brown Lime	4182
Lansing	4200
Base Kansas City	4560
Cherty shale	4688
Cherty sand	4706
Reworked Mississippi	4726
Kinderhook	4795