


9-319W Map No. K-78



S-T-R 16-28S-34W  
SPOT C SE SE  
CO HASKELL (Ks)  
ELEV 3045 DF  
(DF Log)

OPER SOCONY MOBIL OIL CO., INC.  
Wichita, Ks.

WELL #1 GUY E. FLETCHER (NNGPCo)  
Graham-Michaelis

FIELD Eubank Ext  
I.P. P 110 BO & tr wtr/24 hrs, Gr 35.5 deg.,

Chest 5442-5504, P 8 BOPD & 2 BWPD, Mrw 5362-  
83, Gr 31 deg. - Dual Completion

Hb	4039 - 994
Tor	4056 -1011
Lan	4138 -1093
Lan-B	4357 -1312
Lan-C	4442 -1397
Lan-D	4546 -1501
Mar	4708 -1663
Cher	4882 -1837
Mrw	5204 -2159
Ches	5398 -2353
Ches sd	5441 -2396
St L	5532 -2487
St L-D	5636 -2591
LTD	5659 -2614

No DST's, No Cores, RTD 5660, Log,  
(Good shows of oil in Chest)  
5" @5654 w/225 sx. w/DV tool @4424 w/100 sx. & 2nd  
DV tool @3121 w/400 sx.  
PBDT 5612, Set BP @5472, Pf 20/5442-5447 (Chest),  
Frac w/6510 Gal "TDO" & 4000# sd (1d 330 B), § sd to  
5472, Lower BP from 5472-5547, Set Model "R" Pkr @  
5389 (-461 BL), CO, Pf 40/5494-5504 (Chest), § 5 BNO &  
3 B filt wtr/15 hrs, Frac 5494-5504 w/150A x 10,630  
Gal "TDO" x 8000# sd x 2000 gal "TDO" x 500# hulls &  
R.A. Material, § on 1d, § 42 BNO & 7 BL/8 hrs (Gr 35.6  
deg), 1% to 6% wtr (All 1d rec), § U/Chest 5442-5447, §  
23 BL & 25 BNO/12 hrs (Gr 36.1 deg), Rec all 1d, §  
avg 3.5 BNO/5 hrs, CO, Set BP @5420 & 11' sd, § dry to  
6 hrs, Frac w/150 A & 18,000 Gal "TDO" x 10,000#

*Data Inc*

(DF Spl)

sd x 1000# hulls x T.A. material (1d 617 B),  
§ on 1d, § 5 BOPH f 1% wtr (Gr. 36.6 deg.), § 62 BLO f  
30 BNO/20 hrs (Mrw) (Gr 35.6 deg.) f 8% wtr, set  
Guiberson Model "A" Prod. Pkr at 5409, Ran Dual strings  
tbg (Chester & Morrow) - SIP (Mrw) 1385# @5320, SIP  
(Chest) 1333# @5400, Prod zones, Mrw 5377-83 & 5362-  
68, U/Chest 5442-47, L/Chest 5494-5504,  
POP, P 25 BNO/12 hrs from Chest, P 110 BNO/24 hrs & 1.8%  
wtr-Chester, Corr Gr 35.5 deg.,  
P 63 BOPD, P 50 1/3 BF/24 hrs, P 42 BOPD & 7 BWPD from  
Mrw 5362-83

Hb	4040
Lan	4140
Mar	4720
Cher	4870
Mrw	5210
Ches	5390
St L	5530
RTD	5660

P 59 BOPD from all zones, P 20 BO NW/24 hrs, (Morr), State Pot: P 8 BOPD f 2  
BWPD, Mrw 5362-83, Gr 31 deg, State Pot: P 110 BO f tr wtr/24 hrs, Gr 35.5 deg,  
Chest 5442-5504, Dual Completion (Morrow & Chest) - COMPLETED on 9-29-65

MISC DATA  
GEOI Warner Sorensen ELEV 3035 GR SPUD DATE 7-2-65  
FTG 3048 KB DRLG COMP \_\_\_\_\_  
SUPPT \_\_\_\_\_ FR by DATA 6-30-65  
CSG 8" @767 w/300 sx. 5" @5654 w/225 sx. COMP by 9-30-65

LIBERAL ELECTRIC LOG TOPS

3045 KB

Winfield 2678 (+367)  
Council Grove 2920 (+125)  
Heebner 4040 (-995)  
Toronto 4056 (-1011)  
Lansing 4138 (-1093)  
"A-1" 4210 (-1165)  
"C" 4356 (-1311)  
"D" 4546 (-1501)  
Marmaton 4712 (-1667)  
Pay Zone 4744 (-1699)  
Morrow 5226 (-2181)  
"S-3" 5358 (-2313) 13/28;  $\phi$  9 BOPD + 20% wtr  
Cherster 5392 (-2353)  
Sand (Opr) 5442 (-2397) 5/8;  $\phi$  83 BOPD + tr wtr  
Sand 5492 (-2447) 16/20;  $\phi$  42 BO + 7 BL/8 hrs  
St. Louis 5532 (-2487)  
TD 5659