

3-28-17W

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6724 EXPIRATION DATE 6-30-83

OPERATOR Cinco Exploration Co. API NO. 15-097-20,924

ADDRESS P. O. Box 3723 COUNTY Kiowa

Victoria, Texas 77903 FIELD Wildcat

** CONTACT PERSON Melvin Klotzman PROD. FORMATION Miss. Osage

PHONE (512) 573-2416

PURCHASER State Geological Survey LEASE Pyle "B"

ADDRESS WICHITA BRANCH WELL NO. #1

DRILLING BEREDCO INC. 330 Ft. from north Line and

CONTRACTOR 660 Ft. from east Line of

ADDRESS 401 E. Douglas, Suite 402 the NE (Qtr.) SEC 3 TWP 28SRGE 17W

Wichita, Kansas 67202

PLUGGING WELL PLAT

CONTRACTOR (Office Use Only)

ADDRESS KCC

TOTAL DEPTH 4850 PBD 4750

SPUD DATE 11/28/82 DATE COMPLETED 12/17/82

ELEV: GR 2157 DF KB 2169

DRILLED WITH (CABLE) (ROTARY) (CABLE) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 454 DV Tool Used? No.

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

JAN 17 1983

CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

MELVIN KLOTZMAN, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

SUBSCRIBED AND SWORN TO BEFORE ME this 14th day of January, 1983.

COMMISSION EXPIRES: 12-07-84

Notary Public, Victoria County, Texas

** The person who can be reached by phone regarding any questions concerning this information.

SIDE TWO

ACQ-1 WELL HISTORY

OPERATOR Cinco Exploration Co. LEASE Pyle "B" SEC. 3 TWP. 28S RGE. 17WFILL IN WELL INFORMATION AS REQUIRED: WELL NO. #1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand Red Bed & Lime	0	460	Heebner	3995
Red Bed & Shale	460'	1470	Toronto	4008
Shale & Lime	1470'	2016'	Douglas	4022
Lime & Shale	2016'	4676'	Iatan	4144
Lime	4676'	4700'	Lansing	4160
Lime & Chert-Sand	4700'	4770'	Kansas City	4241
Lime±	4770'	4850'	Base/Kansas	4516
			Marmaton	4534
			Cherokee	4652
			Cherokee Sd.	4676
			Miss. Osage	4694
			Kinderhook Sh	4734
			Kinderhook Sd	4762
			Viola	4822
TOTAL ROTARY DEPTH 4850'			Ran GR Induction Log, from 4848 to 454. Ran Neutron Density from 4848 to 2277 with Cyberlook.	
DST #1 4139-4163 (Lansing) 30/60/45/90 IH - 2098 FH - 2001 IF - 56/56 ISIP - 389 FF - 56/69 FSIP - 665 Recovery: 90' mud, no shows				
DST #2 4655-4676 Cherokee 30/60/45/90 IH - 2348 FH - 2348 IF - 42/28 ISIP - 83 FF - 42/42 FSIP - 69 Recovery: 15' mud, no shows				
DST #3 4661-4700 (Cherokee-Miss.) 30/60/45/90 IH - 2237 FH - 2237 IF - 56/70 ISIP - 1561 FF - 56/83 FSIP - 1561 Recovery: 285' of gas cut mud, 47 MCF on 1st flow, 95 MCF on 2nd flow				

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or ~~(Used)~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½"	8-5/8"	24#	454	Lite	250	3% CC
					Class H	100	2% Gel, 3% CC
Production	7-7/8"	4½"	10.5#	4849	Class H	50	5# Gilsonite per s.
					Lite	125	.9 gal. latex per 2% CC in water

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3 1/8" Csq. gun	4764-68, 4770-73, 477
TUBING RECORD			2	3 1/8" Csq. gun	4715-24
Size	Setting depth	Pecker set at			
2 3/8"	4700'		BP At 4758'-4764'-68' Non Commercial		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 gal. HCL + N.E. + Clay stabilizer	4764-4779
1000 gal. HCL & Frac w/33,500 gal. foam (N ₂) 25,550# sand	4715-4724

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity (Gas)
12/17/82	Flowing	.650
Estimated Production -I.P.	Oil	Gas
	0 bbls.	331 MCF
Water	%	Gas-oil ratio
	4	No oil
Disposition of gas (vented, used on lease or sold)	Perforations	
Waiting on pipeline	4715-24' GP	

3-52-14m


3-28-17w ^{PI}

GAS WELL
BACK PRESSURE CURVE

County Kiowa Field Wildcat
Operator Cinco Exploration Company
Lease Pyle B Well No. 1
Volume 830 MCF/24 hr.
Date Tested 12/19/82

DIETZGEN CORPORATION
MADE IN U.S.A.

NO. 340-L33 DIETZGEN GRAPH PAPER
LOGARITHMIC
3 CYCLES X 3 CYCLES



← Q in MCF per DAY →

$\theta = 58$ $n = .625$

STATE COMMISSION

JAN 17 1983

CONSERVATION DIVISION
Wichita, Kansas