

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

29-28-17W


Company - STANOLIND OIL AND GAS COMPANY
Farm - L. C. Ropp No. 1

SEC. 29 T. 28 R. 17W
NEc. NW
330' SN1 & 330' EWI NW $\frac{1}{4}$

DISCOVERY WELL

County. Kiowa

KANSAS



Elevation. 2236 feet + 1/2

Production. 7,300,000 Gas

Total Depth. 5163' PB 4853'
Comm. 6-29-47 Comp. 8-28-47
Shot or Treated. Acid.
Contractor.
Issued. 11-8-47

CASING:

13-3/8" 199' Com. w/ 225 sx
8-5/8" 1157' Com. w/1000 sx
5-1/2" 5018' Com. w/ 300 sx

Figures indicate Bottom of Formations.

collar	0-19	Tops:	
clay	105	Lansing	4277
sand	120	Miss.	4841
shale & shells	200	Viola	4959
sand	220	Simpson	5088
shale	385	Arbuckle	5147
red bed	860		
red bed & shale	1015	Drill Stem Test	4851
shale & shells	1136	Packer set at	4826
anhydrite	1156	Drill Stem Test	4851
lime	1230	Packer set at	4827
shale & shells	1655		
salt	1685	Perf. Casing	
shale & shells	2320	w/72 shots	4942-4960
lime	2345	w/28 shots	4896-4903
shale & lime	2395	w/40 shots	4870-4880
lime	2955	w/32 shots	4858-4866
lime & shale	3105	w/44 shots	4843-4854
lime	3185		
shale & lime	3200	Acid. w/5000 gal. 15% acid.	
lime	3350		
lime & shale	3569	Perf. casing	4839-4845
lime	3686	4 shots per foot	
shale	3695		
lime	3707	Test: (Restricted to 1000 MCF per day)	
shale	3750	6 1/2 hrs through separator at rate	
lime	3764	of 1000 MCF per day.	
shale	3771	Water-107 bbls per day.	
brkn	3790		
lime	4161		
lime & shale	4181		
lime	4187		
lime & shale	4294		
lime	4412		
lime sft	4420		
lime & chert	4474		
lime	4489		
lime & chert	4568		
lime	4815		
lime & chert	4881		
shale	4886		
chert	4907		
lime	4918		
lime & chert	4923		
lime & shale	4955		
lime & chert	4965		
lime sdy & chert	4969		
lime	4988		
lime & chert	5034		
lime	5084		
lime & chert	5093		
lime	5148		
dolomite	5163		
Total Depth			

Plugged back to 4853