


19-28s-17w



DRILL STEM TEST REPORT

Prepared For: **Advantage Resources Inc**

1775 Sherman St Ste #1700
Denver CO 80203

ATTN: Tom Pronald

19 28 17 Kiowa KS

Wynona Ross # 3

Start Date: 2007.06.21 @ 09:29:17

End Date: 2007.06.21 @ 15:06:47

Job Ticket #: 26979

DST #: 1

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 23 2007

CONSERVATION DIVISION
WICHITA, KS

15-097-21611


SW SE NW

2100 FWL 1800 FWL

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Advantage Resources Inc

1775 Sherman St Ste #1700
Denver CO 80203

ATTN: Tom Pronald

Wynona Ross # 3

19 28 17 Kiowa KS

Job Ticket: 26979

DST#: 1

Test Start: 2007.06.21 @ 09:29:17

GENERAL INFORMATION:

Formation: **Mississippi**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 11:44:17

Time Test Ended: 15:06:47

Test Type: Conventional Bottom Hole

Tester: Jerry Adams

Unit No: 36

Interval: **4832.00 ft (KB) To 4846.00 ft (KB) (TVD)**

Total Depth: 4846.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Fair

Reference Elevations: 2211.00 ft (KB)

2206.00 ft (CF)

KB to GR/CF: 5.00 ft

Serial #: 6798

Inside

Press@RunDepth: 35.69 psig @ 4833.00 ft (KB)

Start Date: 2007.06.21

End Date:

2007.06.21

Capacity: 7000.00 psig

Last Calib.: 2007.06.21

Start Time: 09:29:22

End Time:

15:06:46

Time On Btm: 2007.06.21 @ 11:43:47

Time Off Btm: 2007.06.21 @ 12:45:17


TEST COMMENT: IF Weak blow Built to 1 "

ISI No blow

FF Very weak surface blow

FSI NA

Pressure vs. Time



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2396.18	113.73	Initial Hydro-static
1	37.44	114.19	Open To Flow (1)
16	35.69	114.95	Shut-In(1)
46	54.64	115.93	End Shut-In(1)
48	39.26	117.34	Open To Flow (2)
61	33.12	117.39	Shut-In(2)
62	2258.62	119.79	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
5.00	Drilling Mud w/Oil specks 100%M	0.02

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Advantage Resources Inc

Wynona Ross # 3

1775 Sherman St Ste #1700
Denver CO 80203

19 28 17 Kiowa KS

Job Ticket: 26979

DST#: 1

ATTN: Tom Pronald


Test Start: 2007.06.21 @ 09:29:17

Tool Information

Drill Pipe:	Length: 4554.00 ft	Diameter: 3.80 inches	Volume: 63.88 bbl	Tool Weight: 2500.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 20000.00 lb
Drill Collar:	Length: 269.00 ft	Diameter: 2.25 inches	Volume: 1.32 bbl	Weight to Pull Loose: 100000.0 lb
			Total Volume: 65.20 bbl	Tool Chased 0.00 ft
Drill Pipe Above KB:	19.00 ft			String Weight: Initial 82000.00 lb
Depth to Top Packer:	4832.00 ft			Final 82000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	14.00 ft			
Tool Length:	42.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		
Tool Comments:				

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Shut In Tool	5.00			4809.00	
Hydraulic tool	5.00			4814.00	
Jars	5.00			4819.00	
Safety Joint	3.00			4822.00	
Packer	5.00			4827.00	28.00 Bottom Of Top Packer
Packer	5.00			4832.00	
Stubb	1.00			4833.00	
Recorder	0.00	6798	Inside	4833.00	
Perforations	10.00			4843.00	
Recorder	0.00	13249	Outside	4843.00	
Bullnose	3.00			4846.00	14.00 Bottom Packers & Anchor

Total Tool Length: 42.00



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Advantage Resources Inc

Wynona Ross # 3

1775 Sherman St Ste #1700
Denver CO 80203

19 28 17 Kiowa KS

Job Ticket: 26979

DST#: 1

ATTN: Tom Pronald

Test Start: 2007.06.21 @ 09:29:17

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 49.00 sec/qt

Cushion Volume:

bbl

Water Loss: 8.79 in³

Gas Cushion Type:

Resistivity: 0.00 ohm.m

Gas Cushion Pressure:

psig

Salinity: 6000.00 ppm

Filter Cake: 0.02 inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
5.00	Drilling Mud w/Oil specks 100%M	0.025

Total Length: 5.00 ft

Total Volume: 0.025 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #: none

Laboratory Name:

Laboratory Location:

Recovery Comments:


DST Test Number: 1

19 28 17 Klow a KS

Advantage Resources Inc

Inside

Serial #: 6798



Trilobite Testing, Inc

Ref. No: 26979

Printed: 2007.06.26 @ 11:19:46 Page 5

CHART PAGE

This is a photocopy of the actual AK-1 recorder chart.

