

Southwind Petroleum Corp.
Fark (L) #1-1
C-S/2 N/2 NW/4
Sec. 1-28-18W
Kiowa County, KS

Drill Stem Tests

- DST #1 3501-3536 (Howard) 30-45-45-60 GTS 2nd Op, Ga 34 MCF/10",
Stab at 27 MCF/40". Rec. 235' VSGCM, 3249' gas in pipe.
ISIP 1162#, FSIP 1183#, IFP 96#-96#, FFP 106#-106#. BHT 122
- DST #2 4180-4202 (Lans. A) 30-60-30-60 (1st OP) GTS/4", GA 265
MCF/14", Decr. to 216 MCF/27". (2nd Op) Ga. 337 MCF/10",
205 MCF/20", 129 MCF/30". Rec. 40' SGCM, 60' G&WCM, 60' VSM&
GCW, 3986' Gas in pipe. ISIP 596#, FSIP 511#, IFP 192-192#,
FFP 160-160#. BHT 121.
- DST #3 4214-4237 (Lans. B) 30-60-45-90, Rec. 20' VSO&GCM, 120' Gas
in pipe. ISIP 138#, FSIP 298#, IFP 75-75, FFP 53-53#. BHT
128.
- DST #4 4737-4786 (Miss.) 45-60-60-90, (1st Op) GTS/20", Ga.
21,800 CFG/25", 27,000 CFG/30", 34,950 CFG/45", (2nd Op)
Ga. 34,000 CFG/10", 39,200 CFG/20", 41,650 CFG/30", 45,500
CFG/50", 47,100 CFG/60". Rec. 50' VSGCM, 4701' Gas in pipe.
ISIP 873#, FSIP 884#, IFP 15-38#, FFP 27-48#. BHT 122.