

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 12-4-81
FORM CP-1
RECEIVED
OCT 27 1982
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
File One Copy

API NUMBER Well Completed 8/21/77 (of this well)
(This must be listed; if no API# is available, please note drilling completion date.)

LEASE OWNER Voyager Petroleum, Inc. 2003

ADDRESS 110 16th Street, Suite 800, Denver, CO 80202 PHONE # (303) - 629-1447

LEASE (FARM NAME) Keller WELL NO. B#1

WELL LOCATION CSESW SEC. 24 TWP. 28S RGE. 18W (East) (West)

COUNTY Kiowa TOTAL DEPTH 4886' FIELD NAME N/A

OIL WELL X GAS WELL INPUT WELL SWD WELL D&A

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? Welex logs previously sent on completion, no additional logs run, well originally drilled by W.B. Osborne in 1974, Voyager re-entry.
(If not, state reason why)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at discretion of plugging agent & contractor;
to be accomplished by November 15, 1982

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leo R. Schueler ADDRESS 110 16th Street, Suite 800, Denver, CO 80202

PHONE # (303) - 629-1447

PLUGGING CONTRACTOR Clark Corporation LICENSE NO. 5107

ADDRESS 107 W. Fowler, Medicine Lodge, KS 67104 PHONE # (316) - 886-5665

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Leo R. Schueler

ADDRESS 110 16th Street, Suite 800, Denver, CO 80202 PHONE # (303) - 629-1447

AND PAYMENT WILL BE GUARANTEED BY APPLICANT /OR ACTING AGENT.

SIGNED: Leo R. Schueler
Applicant /or Acting Agent

DATE: October 25, 1982



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202

JOHN CARLIN
L. C. LOUX
W. T. ROY
WILLIAM R. DICK
AROLD J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

THIS PERMIT

October 29, 1982

JAN 29 1983

EXPIRES

WELL PLUGGING AUTHORITY

Keller 'B' #1
C SE SW 2
Sec. 24-48S-18W
Kiowa
T.D. 4886'
Clark Corporation


Voyager Petroleum, Inc.
110 16th Street
Suite 800
Denver, CO 80202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,


DELBERT J. COSTA, Administrator

Dist. #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760
is hereby assigned to supervise the plugging of the above named well

NOTE: If you are unable to contact District Plugging Agent at his regular number, call TOLL FREE 1-800-362-1358.

API NUMBER 15-

C SE SW, Sec. 24, T 28 S, R. 18 W

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7462

Lease Name *Keller 'B'* Well # *1*

Operator: Voyager Petroleum, Inc.
Name & Address 110 16th Street
Suite 800
Denver, CO. 80202

County Kiowa

Well Total Depth 4886 feet

Conductor Pipe: Size feet

Surface Casing: Size $8 \frac{5}{8}$ " feet 350

Abandoned Oil Well ☒ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated

Plugging Contractor Clark Corporation License Number 5105

Address Medicine Lodge KS

Company to plug at: Hour: 9:30 am Day: 7 Month: 2 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO ELMO Morgenstern

(company name) Clark Corporation (phone) 316-886-5565

were: Sanded hole to 4790 add 45x Cement. Top
of cement 3650. Recovered Pump 45x hulls -
15 gel - 50 5x cement - 15x hulls - 15 gel - 1 wire
plug - 100 5x cement pumped into ~~per~~ surface
after recovering 4 1/2" production string

Signed Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None ☒

Operations Completed: Hour: ~~4:30~~ ^{11:40} AM Day: 7 Month: 2 Year: 1983

ACTUAL PLUGGING REPORT *Plugged as Ordered*

Recovered 2442' of 4 1/2" production casing

100 psi. Shut in pressure

1500 psi Max. pumping pressure

Dowell did the cementing

Bob Tarbutton gave orders

Remarks: Perforations at 4840' to 4867'

RECEIVED
STATE CORPORATIONS COMMISSION

FEB 10 1983

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kiowa SEC. 24 TWP. 28S RGE. 18W E/W
Location as in quarters or footage from lines:
C - S-E - S-W

Locate Well
correctly on above
Section Platt.

Lease Owner Voyager Petroleum
Lease Name Keller Well No. B-1
Office Address 110 16th St./Suite 800/Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 8/21/1977
Application for plugging filed 10/25/1982
Plugging commenced 1/15/1983
Plugging completed 2/7/1983
Reason for abandonment of well or producing formation Dry

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Durant / Tarbutton
Producing formation _____ Depth to top _____ bottom _____ T.D. 4886'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	350	none
				4 1/2	4886	2442

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Plugged back at 4850. Sand from 4850 to 4790. Dumped 4 sacks of cement with dump bailer from 4790 to 4760. Ripped at 3000 - 2900. Pipe moving, then stopped. Had to rip at 2600 and 2424 before pipe came free. Dowell pumping. Top plug. 4 sacks of hulls. 15 sacks of jell. 50 sacks of cement. 15 sacks of jell. 1 sack of hulls. Plug. 100 sacks of cement. 4% jell. 3% c.c. I talked to Bob Tarbutton for top 50 - 50 - Poz. Randy on location. Plugged 2/4/1983 at 10:00 a.m.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corp.

STATE OF Kansas COUNTY OF Barker, ss.
Edward R. Mogenstern (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Edward R. Mogenstern
(Address) Medicine Lodge, Mo.

SUBSCRIBED AND SWORN TO before me this 8th day of February, 19 83

My Commission expires: April 4, 1986.

RECEIVED
STATE OF KANSAS
Notary Public.

FEB 14 1983

CONSERVATION DIVISION
Wichita Kansas