

*Geological Survey*  
**WICHITA BRANCH**  
**6-28-18W**

CONTRACTORS WELL LOG

API 15-097-20419

OPERATOR: TGT Petroleum Corp. *←*  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: COLCLAZIER #2  
 LOCATION: 100' W. of C SE NW -Sec. 6-28S-18W  
 Kiowa County, KS  
 SPUD DATE: 10/03/81  
 COMPLETION DATE: 10/19/81

0	430	Sand
430	1015	Sand & Red Beds
1015	2447	Red Beds & Shale
2447	4255	Lime & Shale
4255	4270	Lime
4270	4380	Lime & SHale
4380	4423	Lime
4423	4760	Lime & Shale
4760	4770	Lime
4770	4790	Lime & Shale
4790	4820	Lime
4820	4845	Lime & Shale
	4845	Rotary Total Depth

Spud hole @ 5:45 p.m., 10/03/81. Drilled 430' of a 12¼" hole. Ran 10 jts. of 8 5/8" 24# casing set @ 430.79' and cemented with 100 sx. Halliburton Lite, 3% c.c., 250 sx. Class A, 2% gel, 3% c.c. Job complete @ 5:00 a.m., 10/04/81.

4845' TD. Ran 122 joints of 5½" 14# casing set @ 4839'. Triplex shoe set 6' off bottom. Cemented with 50 sx. Halliburton Lite, 12½# Gilsinite per sx. Followed with 200 sx. 50-50 posmix. Salt Saturated. Plug was down @ 2:45 p.m., 10/19/81.

SAMPLE TOPS:

Anhydrite 1168'  
 B/Anhydrite 1190'

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

**RECEIVED**  
**STATE CORPORATION COMMISSION**  
**OCT 29 1981**  
**CONSERVATION DIVISION**  
*Wichita, Kansas*

Jack L. Partridge, Vice Pres. of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the COLCLAZIER #2, 100' W of C SE NE, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.  
 BY: *Jack L. Partridge*  
 Jack L. Partridge, Vice Pres.