



SIDE TWO

Operator Name HILLENBURG OIL COMPANY Lease Name COLCLAZIER Well # 5

Sec. 6 Twp. 28 Rge. 18  East  West Country KIOWA

WELL LOG

METHOD OF COMPLETION

Production Interval

Disposition of gas:  Vented  Open Hole  Perforation  
 Sold  Other (Specify) .....  
 Used on Lease

Drill Stem Tests Taken  Yes  No  
 Samples Sent to Geological Survey  Yes  No  
 Cores Taken  Yes  No

Formation Description

Log  Sample

Name	Top	Bottom
From 2236' KB		
Heebner		4048
Toronto		4063
Douglas Shale		4084
Brown Lime		4201
Lansing		4212
BKC		4553
Marmaton		4614
Cherokee		4728
Mississippi		4782
Kinderhook		4826


Estimated Production Per 24 Hours	Oil	Gas	Water	Gas-Oil Ratio	Gravity
60 Bbls		MCF	None	Bbls	CFPB

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	12-1/4	8-5/8	24#	456	Common	315	3% cc. 2% gel.
Production	7-7/8	5-1/2	17#	4896	Com/Poz.	150	2% gel.

PERFORATION RECORD		Acid, Fracture, Shot, Cement Squeeze Record	
Shots Per Foot	Specify Footage of Each Interval Perforated	(Amount and Kind of Material Used)	Depth
2	4826 - 4842		

TUBING RECORD	Size	Set At	Packer at	Liner Run	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
	2-3/8	4855			

Date of First Production 5-16-85 Producing Method  Flowing  Pumping  Gas Lift  Other (explain).....



6-28-18W

# WHITE

AND ELLIS DRILLING, Inc.

## DRILLERS LOG

OPERATOR: Hillenburg Oil Co.  
 116th & S. Lynn Lane  
 Broken Arrow, OK 74012

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,  
 Wichita, Ks. 67202

Lease Name Coclazier Well No. 5

Sec. 6 T. 28S R. 18W Spot C N/2 NE NW

County Kiowa State Kansas Elevation \_\_\_\_\_

### Casing Record:

Surface: 8 5/8 @ 456 with 2% gel <sup>3% cc</sup> 300 sx.

Production: 5 1/2 @ 4896 with 150 sx.

Type Well: Oil Well Total Depth 4897

Drilling Commenced 4-29-85 Drilling Completed 5-7-85

Formation	From	To	Tops
Cellar	0	7	
Sand	7	456	
Lime, Shale	456	4897	

MAY 24 1985  
 State Geological Survey  
 WICHITA BRANCH

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 24 1985

CONSERVATION DIVISION  
 Wichita, Kansas