

A-7-139


FIRST REPORT AND COMPLETION

MAP NO. _____ ELEV. 3041 DF
 STATE Kansas COUNTY Haskell sec. 20 Twp 28S Rge 34W
 OPERATOR Northern Natural Gas Co. LOC. NW NE
 WELL NO. 2 FARM NAME Clark "C" FT. FROM _____ LINE _____
 TOL Eubank FT. FROM _____ LINE _____
 FR. _____ SPUD _____ COMP. 7-13-61

CONT./GEOI.

NAME PRODUCING INTERVAL	COMPLETION RECORD		PERF. W/HOLES	TREATMENT RECORD
	FROM - TO			
<u>Lansing</u>	<u>4522-28</u>		<u>24</u>	<u>1000 MA</u>
b				
c				
d				

d I. P. OIL/DIST. WTR. AOF GAS 856 M.C.F.P.D. _____ CHK. 18/64" HRS. _____
 b " " " " " " "
 c " " " " " " "
 d _____



D & A ()

SIP# 1365 # FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBTD 4574 TD 5650
 SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.
5-1/2" 5432 675 _____ _____ _____

OPERATOR Northern Natural Gas Co. No. #2 Clark "C" ELEV. 3041 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Heebner	4006	
			Toronto	4026	
			Lansing	4104	
			Marmaton	4718	
			Cherokee	4867	
			Morrow	5214	
			Morrow Sand	5370-92	
			Chester Sand	5454	
			Ste Genevieve	5503	
			St Louis	5628	

Old Info: OTD 5650. 5-1/2" @ 5432 w/675 sx. Was completed as Morrow oil well (5371-80).

New Info: MICT. pulled tbg. Set Plug @ 5100.

P/12/5062-65 (Chero) 1000 MA, Swb ld, FV w/100 fluid/per hr. (85% wtr). Set Plug @ 4650.

P/12/4597-4600 (Lans) 1000 MA, FV w/wtr, Set Plug @ 4574.

P/24/4522-28 (Lans), 2-3/8" tbg @ 4537, 1000 MA, SICP 1500#, 20" of 2,830 MCF/O, FCP 425#.

IP AOF 856 MCF/O, 18/64" ck, SITP 1365#, From Lans (4522-28).

COMPLETE 7-13-61.