

5-28-21W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BEN J. TAYLOR
Farm- Blurton

No. 1

SEC. 5 T. 28 R. 21W
C NE NE

Total Depth. 5035'

Comm. 8-4-58


Comp. 8-24-58

Shot or Treated.

Contractor. Armer, Inc.

Issued. 11-1-58

County Ford KANSAS



CASING:

8" 198'

Elevation. 2328' DF

Production. DRY

Figures Indicate Bottom of Formations.

sand, red & blue shale	198
shale, shells	545
anhydrite	560
red bed, shale, shells	1257
shale, shells	1330
lime anhydrite	1373
shale, shells	1395
shale, shells, red bed	1655
shale, shells	1795
shale, shells, lime	2130
shale, lime	2520
lime	2570
lime, shale	3315
lime	3383
shale, lime	3880
sdv lime	3915
lime	3970
lime, shale	4055
lime	4127
lime, shale	4435
lime	4510
lime, shale	4578
lime	4604
lime, shale	4685
lime	4700
lime, shale	4760
lime	4800
lime, shale, cherty	4825
lime, shale	4880
lime, chert	4914
lime, shale, cherty	4937
lime, shale	4990
lime	5035
Total Depth	

TOPS:

Lansing Kansas City	4258
Mississippi	4932