

15-057-20112

State Geological Survey

WICHITA BRANCH
KANSAS DRILLERS LOG

S. 14 T. 28S R. 21 E
Loc. 1570' FSL & 1320' FWL
County Ford

API No. 15 — 057 — 20,112
County Number

Operator
Texas Oil & Gas Corp.

Address
200 W. Douglas, Suite 300, Wichita, Kansas 67202


Well No. 1 Lease Name Mann "B"

Footage Location
1570 feet from (N) (S) line 1320 feet from (E) (W) line

Principal Contractor Xplor Drlg. Co. Geologist High Plains Consulting Ltd.

Spud Date 2-15-78 Total Depth 5200' P.B.T.D. N/A

Date Completed 2-28-78 Oil Purchaser N/A



Elev.: Gr. 2374'
DF 2379' KB 2382'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	581'	Common	550	2% Ge1, 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			
TUBING RECORD			N/A	N/A	N/A
Size	Setting depth	Packer set at			
N/A	N/A	N/A			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
N/A	N/A

INITIAL PRODUCTION

Date of first production N/A	Producing method (flowing, pumping, gas lift, etc.) N/A
RATE OF PRODUCTION PER 24 HOURS	Oil N/A bbls. Gas N/A MCF Water N/A bbls. Gas-oil ratio N/A CFPB
Disposition of gas (vented, used on lease or sold) N/A	Producing interval (s) N/A

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Texas Oil & Gas Corp.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Mann "B" Dry Hole

S 14 T 28S R 21 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herrington	2598	-216		
Cottonwood	3111	-729		
Topeka	3829	-1447		
Heebner	4140	-1758		
Lansing	4336	-1954		
Swope	4658	-2276		
Hertha	4700	-2318		
Mississippi	5005	-2623		
TD	5200	-2818		
DST #1, 3836-3904', (Topeka) w/results as follows: IFP/30": 116-487#, strong blow; ISIP/60": 1269#; FFP/45": 591-841#, strong blow; FSIP/90": 1269#; Rec 1920' SW.				
DST #2, 5019-86', (Mississippi) w/results as follows: IFP/30": 213-448#, GTS/20", 31.6 MCFD; ISIP/60": 1506#; FFP/45": 575-815#, gauged 14.4 MCFD; FSIP/90": 1527#; Rec 120' GCM, 180' WCM & 1606' SW.				
DST #3, 4965-5046', (Mississippi) w/results as follows: Misrun.				
DST #4, 4965-5046', (Mississippi) w/results as follows: IFP/30": 60-72#, fair blow; ISIP/60": 151#; FFP/30": 91-91#, fair blow; FSIP/60": 111#; Rec 120' DM.				
DST #5, 2904-44', (Wreford) w/results as follows: IFP/30": 30-87#, weak blow; ISIP/60": 634#; FFP/45": 113-131#, fair blow; FSIP/90": 640#; Rec 496' MSV.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Harold A. Brown
 HAROLD A. BROWN Signature
 District Geologist Title
 February 28, 1978 Date