

PI

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 057 — 20,184
County Number

S. 14 T.28S R.27E

Loc. State Geological Survey
County Wichita BRANCH
Ford

Operator

Wells Energy Corp.

Address

700 South Colorado Blvd., Suite 454 Denver, CO

Well No.

2

Lease Name

Vice

80222

Footage Location

480 feet from (N) (S) line

2310

feet from (E) (W) line, NE 1/4

Principal Contractor

H-30, Inc.

Geologist

Michel Russell

Spud Date

10/30/80

Date Completed

11/27/80

Total Depth

5140'


P.B.T.D.

5094'

Directional Deviation

Oil and/or Gas Purchaser

Kansas Gas Supply Co.

640 Acres
N

Locate well correctly

Elev.: Gr. 2361'

DF _____ KB 2373'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surf.	12 1/4"	8 5/8"	24#	667'	Common	550	
Prod.		4 1/2"	10.5#	5138'	RFC	100 sx-1st stage 125 sx-2nd stage	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4		5041'-44'

Size	Setting depth	Pecker set at
2 3/8"	4960'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Perf. 5041'-44'; Acd. w/1500 gal. 15% mud acid	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
SI	Flowing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	-	2500	-	Negligible
	bbis.	MCF	bbis.	CFPB

Disposition of gas (vented, used on lease or sold)	Producing interval(s)
SI	5041'-44'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Wells Energy Corp. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: SI Gas Well

Well No. 2 Lease Name Vice

S 14 T 28 S R 21 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			Dual Ind.-Laterolog	
			G/R Neut.-Density w/ caliper	
			Heebner	4166 (-1793)
			Lansing	4318 (-1945)
			Mississippi	4986 (-2613)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

[Signature]
Signature

President
Title

February 18, 1981
Date

