

22-28-21W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO. & RUPP-FERGUSON OIL CO.
Farm- Karns Unit No. 1

SEC. 22 T. 28 R21W
SW NE NE
1250' fr NL 1250' fr E1 NE

Total Depth. 5132'
Comm. 3-30-57 Comp. 4-15-57
Shot or Treated.
Contractor. Rupp-Ferguson Oil Co.
Issued. 6-8-57

County Ford KANSAS



CASING:
8 5/8" 375'w/225 sx cem.

Elevation. 2373' DF

Production. Dry

Figures indicate Bottom of Formations.

sand	145
shale	375
sand	390
red bed	575
anhydrite	595
salt-shale	820
red bed	1365
red bed-shale	1650
lime-shale	2523
lime	2850
lime-shale stks	2905
lime-shale	4244
red shales-brwn lime-	
stone	4355
shale	4397
lime	4454
limestone	4466
lime	4494
limestone-	4499
lime	4620
limestone	4630
lime	4678
limestone	4684
lime-shale	4738
lime	4861
lime-shale	5027
quartz-chert-grn	
shale	5042
limestone-chert	5080
chalky limestone-	
some chert	5132
Total Depth	

Mississippi Detrital 5031 5028
Mississippi lime 5049 5051

DST #1 - 5027-5042', open 30 min.
weak blow & died, rec. 12' drilling
mud, all pressures were Off.

DST #2 - 5042-5080', open 1 hr., weak
initial blow & died, rec. 14' drilling
mud, IFP-90#, FFP-60#, BHP-Off.

TOPS:	Sample	Elec.
Heebner shale	4205	4204
Toronto lime	4226	4226
Douglas	4244	4244
Brown lime	4355	4357
Lansing-Kansas City	4363	4366
B/Kansas City	4758	4758
Ma rmaton	4809	4808