

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

S. 25 T. 28 R. 21 ~~X~~ W

API No. 15 — 057 — 20,057
County Number


Loc. C SW

Operator
Halliburton Oil Producing Company

County Ford

Address 117 Cameron Bldg.
Oklahoma City, Oklahoma 73106

640 Acres
N



Well No. # 1 Lease Name Chalfant

Elev.: Gr. 2365

Footage Location
1320 feet from NE (S) line 1320 feet from NW (W) line

DF 2370 KB 2371

Principal Contractor Sage Drilling Company Geologist Bob Crumpley

Spud Date 10-13-73 Total Depth 5050 P.B.T.D. 5050

Date Completed 11-21-73 Oil Purchaser None

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	20	530	Regular Litewt.	100	3% C.C.
Production	7 7/8	5 1/4	14	5026	Pozmix	125	18% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None			None -	Open Hole	

TUBING RECORD

Size	Setting depth	Packer set at
2"	4965	4965

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2000 gal. NE Acid	5026-5050

INITIAL PRODUCTION

Date of first production 11-15-73	Producing method (flowing, pumping, gas lift, etc.) Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls.	Gas 4200 MCF	Water 0 bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) Buyer not determined			Producing interval(s) 5026-5050	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator: Halliburton Oil Producing Company

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas

Well No. # 1 Lease Name Chalfant

S 25 T 28 R 21 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
(Chase Group)	2611	2990	Herrington Krider Winfield	
Limestone & dolomitic limestone, cherty in part	2990	3460	Towanda Ft. Riley Florence Wreford	
(Council Grove Group)	3460	4250	Council Grove Neva Foraker Tarkio Howard Topeka Heebner Toronto	
Primarily Limestone with Occasional thin shales				
(Douglas Group)	4250	4360		
Shale, sand & limestone				
(Missourian Series)	4360	4806	Brown Lime	
Limestone with occasional streaks of shale			Lansing	
(Marmaton Group)	4806	4926	Marmaton	
Alternating limestones, cherty, and shales				
(Cherokee Group)	4926	5016	Cherokee	
Limestones, dark, cherty, pyritic & black shales				
(Mississippian)	5016	5024	Mississippian	
Limestone				
Dolomite & dolomitic limestone	5024	5051		

DST # 1 5026-5051 - Gas in 1 minute, 6,880 MCF
 IF 1175 FF 912 ISIP 1623 FSIP 1610
 CAOF 13,084 MCFD

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



J. D. Swanson
 Signature

Production Superintendent
 Title

1-14-74
 Date