

36-28-22W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY TIME PETROLEUM

SEC. 36 T. 28 R. 22W

FARM Cook

NO. 1

LOC. C NW SE

TOTAL DEPTH 5244'

COMM. 8-11-64

COMP. 8-30-64

SHOT OR TREATED

CONTRACTOR Strata Drilling

ISSUED 12-16-67

COUNTY Ford

KANSAS

CASING

20

10

15

8

5/8" 274' cem w/ 250 .sx

ELEVATION 2447' DF

12

6

13

5

PRODUCTION 19 BO PLUS 10 BWPD

4 1/2" 5243' cem w/ 75 .sx

Miss Chat 5173-77

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	0	130
Clay & Shale	130	432
Sand	432	490
Shale	490	562
Sand	562	592
Shale	592	845
Shale & Red Bed	845	1070
Shale & Shells	1070	1635
Shale	1635	2470
Lime	2470	3040
Lime & Shale	3040	4480
Kansas City Lime	4480	4539
Lime	4539	5153
Lime & Chert	5153	5244

Ran 274' of used 8-5/8" surface casing set and cemented at 232' with 250 sacks of regular cement, 2% gel and 3% calcium chloride. Plug down at 7:15 A. M. August 12, 1964. Cement circ..

Total Depth 5244'	
TOPS: LOG	
Anhydrite	634
Chase Group	2693
Base Kansas City	4910
Cheorkee	5049
Mississippi chat	5173

Ran Electra log.

Ran 160 joints of new 4 1/2" casing (5243.42'); set and cemented at 5243' with 75 sacks of 60-40 peckin, salt saturated, 10 barrels of salt flush ahead of plug. Plug set at 5218' at 1:00 P. M. August 30, 1964.



STATE OF KANSAS)
COUNTY OF BARTON) ss.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.