

4-43W

MAP NO. 78SEC. 22-28S-34WSTATE Kans. COUNTY HaskellLOC. C NW SWOPER. W. J. Coppinger, Wichita, Kansas

FT/FR _____ LINE

WELL #2 FARM Lucas

FT/FR _____ LINE

Eubank

ELEV. 3040 GR. 3042DF 3045

KB

K. & E. Drlg. Tools

GEOL. Wayne BrinegarCO. INT. 5700' testF.R. 1/22/64 SPUD 1/29/64 COMP. 4/7/64TD 5660 FM. Chest PBTD _____

PRODUCING FM.

FROM

TO

PERF
W/HOLES

TREATMENT

Miss 5510-24½46750AI.P. State Pot: 120 BOPD, NW, Grav. 40.8 deg.Completion
RecordCasing
Record8-5/8" @ 785 w/400 sx.4½" @ 5658 w/150 sx.*Data Inc.*

KB Spl Tops:

Anh	1831	+1215	Lans	4147	-1102	Mrw sd	5380	-2335
Hb	4052	-1007	Marm	4732	-1687	Chest	5460	-2415
Tor	4071	-1026	Cher	4884	-1839	RTD	5660	-2615

DST #1 (Mrw) 5355-5420, Op 1 hr., R 20' M, ISIP 90#/30", IFP 55#
 IFP 58#, FSIP 75#/45"

Ø #1 (Ches) 5463-5521, Rec. mostly interbedded sh & sd, sd 5507-21
 w/good poro & GSO
 Ø #2 (Ches) 5521-73, Rec all lm w/some v poor poro & dead oil stn
 RTD 5660, Log, 4½" @ 5658 w/150 sx., DV @ 300' w/150 sx. MICT,
 Pf Mrw 16/5510-14 & 30/5517-25½, No flu, Nat, 750 MCA w/tracer
 survey - chann. § pt ld, Sqz 5510-24½ w/150 sx., Re-pf 16/5510-14
 & 30/5517-24½, § 12½ BOPH w/tr wtr/13½ hrs, POP, State Pot: P 120
BOPD, NW, Grav. 40.8 deg., Miss 5510-24½, COMPLETE (4/1/64)

LIBERAL ELECTRIC LOG TOPS

3045 KB

Winfield 2688 (+357)

Heebner 4058 (-1013)

Toronto 4072 (-1027)

Lansing 4148 (-1103)

"D" Zone 4566 (-1521)

Marmaton 4704 (-1659)

Pay Zone 4738 (-1693)

Morrow 5214 (-2169)

"S-3" Sand 5380 (-2335) 4/14; tst mud

Chester 5408 (-2363)

Sand 5508 (-2463) 14/14; ϕ 120 BO

Ste. Gen 5522 (-2477)

St. Louis 5582 (-2537)

TD 5660