



Perf 6/5492-94, 12/5482-88, 8/5445-49, 10/5462-67, 16/5484-92 (Chester); \$ 3 BOPH from each zone, A/2000 (all zones), \$ 1d, \$ 3 BOPH/7 hrs, \$ 2½ BOPH/12 hrs, A/5000, \$ est 25 BOPD from Chester and St. Louis zones, PB 4230, 4 way jet @ 4192 (KC) Perf 32/4169-77 (KC), A/500 M, \$ 1d, \$ 17 BOPH-NW/4 hrs, POP (KC Producer only - Chester and St. Louis zones are plugged off), P 100 BOPD-NW; State Pot: P 123 BOPD-NW, G. 36°, KC 4169-77 and 4192, Comp. 12/10/62.

NEW INFO: Pull T&R, CO pl @ 4230, ran tbg w/RTTS pkr @ 5330 frac St. Louis & Chester perfs thru tbg w/20,000 gal crude x sd/10,000#, flo 1d, flo 12 BOPH-NW/16 hrs, pull tbg & RTTS pkr, ran tbg w/prod pkr @ 5330 to produce Miss, hang tbg to produce KC, POP, Dual Completion - State Pot: P 123 BOPD-NW, G. 36° from Lans and P 160 BOPD & tr wtr (G. 38.2°) from Miss - First reported and completed.

*See other ticket*