


10-276W MAP NO. 78 SEC. 22-28S-34W
 STATE Kans COUNTY Haskell LOC. C SE SW
 OPER. W.J. Coppinger - Wichita, Kansas FT/FR _____ LINE _____
 WELL 1 FARM Lucas FT/FR _____ LINE _____
 TOWN Eubank ELEV. 3024 GR. 3026 DF. 3029 KB _____
 CO. K&E Drlg. GEOL. Wayne Brinegar
 INT. North, Nat. Gas Farmout 3600' Miss Test
 F.R. 6-17-63 SPUD 7-8-63 COM. 10-22-63
 TD 5685 FM. St Louis PBD. 5490



Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		<u>Chester</u>	<u>5462½-5480</u>	<u>36</u>	<u>Natural</u>
	<u>IP State Pot: P 110 BOPD + 2% wtr (no gr avail)</u>				
Casing Record	<u>8" @770 w/425 sx.</u>		<u>4½" @5669 w/200 sx.</u>		

Data Inc.

(KB Spl)		(KB Log)	
Hb	4064	Mrw sd	5234
Tor	4088	Chest	5400
Lans	4158	St Lou	5552
Marm	4756	RTD	5685
Cher	4894		
Mrw sh	5234		
			(Cont)
WLT #1 (Ches sd)	5474-76½, Op 90",	Mrw sd	5343
R 15,400 cc filt wtr w/sli		Chest	5359
fluor, ISIP 1550#/15", SP 0-50#,		" sd	5439
FSIP 1530#/5"		St Lou	5542
WLT #2 (Ches sd)	5346½-49, Op 2	"D" zn	5628
hrs, R 15,400 cc filt wtr w/sli		LTD	5682
fluor, ISIP 1550#/20", SP less than			
50#, FSIP 1530#/10"			
DST #1 (Ches sd)	5502-15 (Str Pkr) Op 1 hr, R 130' filt wtr,		
ISIP 1521#/45", IFP 16#, FFP 50#, FSIP 1258#/45",	4½" @		
5669 w/200 sx. + DV tool @2982 w/150 sx., MICT, § dn, Collar			
log, 3 way jet @5533 (Chest), § 2 BFPH (90% wtr + 10% oil)/6			
hrs, Sq 5533 w/125 sx., Perf 36/5504-13 (Chest), 2 1/3 BOPH-NW			
/6 hrs, nat, 500A + frac 12,000 GO x 3500# sd x 250# walnut			
hulls, R 270 B ld/6½ hrs, Plg @5490, Perf 28/5473-80, 8/5462½-			
64½ (Chest), § 13 BOPH/6 hrs - POP - natural, Ran tbg @5468,			
PBD 5490, POP (Will Prod perfs 5462½-80 only), P 105 BOPD +			
tr wtr, State Pot: P 110 BOPD + 2% wtr, Chest 5462½-5480 -			
COMPLETED (10-16-63)			

LIBERAL ELECTRIC LOG TOPS

3029 KB

Winfield 2680 (+349)

Heebner 4058 (-1029)

Toronto 4078 (-1049)

Lansing 4152 (-1123)

"D" Zone 4576 (-1547)

Marmaton 4712 (-1683)

Pay Zone 4750 (-1721)

Morrow 5222 (-2193)

"S-3" Sand 5322 (-2293) 5/22; WLT filt. wtr + sho fluor

Chester 5350 (-2321) ϕ P 110 BOPD + 2% Wtr.

Sand 5440 (-2411) 53/100; \$ 13 BOPH/6 hrs

St. Louis 5542 (-2513)

TD 5685