

90091

A-9-77

MAP NO.

ELEV. 3074 DF

STATE Kansas COUNTY Grant SEC. 23

Blk 28S Rge 38W

OPERATOR Pan American Petroleum Corp.

LOC. C NW SE

WELL NO. 1 FARM NAME Schartz GU

FT. FROM LINE


COL WC (Geol WC in Panama Gas Area) (PD 5600)

FT. FROM LINE

FR. 8-4-61 SPUD 8-3-61 COMP. 8-30-61

CONT./GEOL. Big Chief Tools

NAME PRODUCING INTERVAL	COMPLETION RECORD		PERF. W/HOLES	TREATMENT RECORD
	FROM	TO		
a				
b				
c				
d				



I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	HRS.
b	"	"	"	"	"
c	"	"	"	"	"
d					

D & A D & A X 1

SIP# FI TP # FI CP# SIBHP

GOR. GR. PBD TD 5700

SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD SIZE	DEPTH	W/SAX.
8-5/8"	1726	1000			

OPERATOR Pan American Petr. Corp. WELL NO. #1 Schartz GU ELEV. 3074 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Missouri	3862		Chase	2316	
Des Moines	4451		Council Grove	2620	
			Pennsylvanian	3060	
			Missouri	3870	
			Des Moines	4450	
			Morrow	5160	
			Morrow Sand	5370-5402	
			Morrow Sand	5490-5504	
			Chester	5504	
			Ste Genevieve	5530	
			St Louis	5618	

Spud 8-3-61. 8-5/8" @ 1726 w/1000 sx. @ 3480, fishing DC. Rc fish
 TD 5700, logs.

WLT #1 @ 4168, op 90 mins, Rc 3375 cc Wtr (less than 5% Fm Wtr),
 ISIP 1220/30 mins, EP less than 50, FSIP 1200/30 mins.

WLT #2 (Mo) @ 3958, op 90 mins, Rc 20,800 cc Wtr/NS, ISIP 1165/15
 mins, FP 0-1000, FSIP 1100/75 mins.

WLT #3 (DM) @ 4636, op 1 hr, Rc 2000 cc Wtr, ISIP 1510/25 mins,
 EP less than 50, FSIP 1510/30 mins.

D & A 8-30-61. COMPLETE.

LIBERAL LOG TOPS

3077 KB

Winfield 2404 (+673)

Council Grove 2642 (+435)

Heebner 3780 (-703)

Toronto 3811 (-734)

Lansing 3884 (-807) WLT filt wtr

Marmaton 4450 (-1474) WLT filt wtr

Morrow 5162 (-2085)

"S-2" 5370 (-2293) 6/20, NT

"S-3" 5490 (-2413) 5/14, NT

Chester 5504 (-2427)

St. Gen 5530 (-2456)

St. Louis 5622 (-2548)

TD 5700 D & A