


State Ks. Field EUBANK
Company WHITE EAGLE County HASKELL
Farm EUBANK No. 2
Sec. 28 Twp. 28 S Range 34 W

Spot SE NW

Contractor RINE

Remarks Miss P.D.



Comm. 7-25-58 Comp. 10/29/58

Elev. DF 3030 GL 3022 KB 3033 TD 5635 PB

Pay Chas 5451-58 (Lan gas 4590-4602 ST)

I.P. F 290 BOPD Press.

Casing Record: 13 3/8 7"

20" 10 3/4 812/800 5 1/2" 5565/500

16" 8 5/8

spud, csg Sample Win +388 Log

1760 TOP 3546 HR -981 4011

AUG 6 TTD 2749-fract HD 4016 LAN -1083 4113

AUG 13 4145 TOP 4033 Chas -1761 4791

AUG 2 ODS 4535-57 LAN 4112 MOR -2176 5206

1' Rec 350' MOR 5209 Re -2409 5439

5GC salty M. "SS 5357-70 " -2422 5452

EP 10-200 " -2429 5459

BHP 1155/20" ST 5489

E 5448-73 ST L 5608

AUG 27 Rec. 25'

4' SS N.S.

7' " sub. w/oil

16% por 30% utn

14' ls N.S.

DST 5448-73

Rec 480' gassy oil +

260' Mud. fill w/oil

EP 50-565

BHP 1430/60"

RTD 5635, log 5631

5 1/2" csg, MIST

SEP 3 C.O.

P/16 5492-5500 N.S., Ac 1000
Swd. Id. + $5\frac{1}{2}$ BNO + 2 BW-1
Ac 1000, frac 9 (5% ac) x 7
Swd 24 BW + 1 BNO/hr.

Br. plug 5485

P/14 5451-58 Swd 4 BNO - 1st hr.
Swd 3 BNO - 2nd hr, ~~prop Ac~~

SEP 10 Ac 500 ma, Swd 25 BNPH
- communication, SQ w/ 300 SX

no-P/14 5451-58 Swd 12-2 BNOPH (nat) - no water

SEP 17 ~~Intg~~ Ac 500 ma, Swd 18.9 BNO-13'

Swd $2\frac{1}{2}$ BNOPH w/ 55G
frac 10x10, flood Id. + Swd Id.
Swd 30 BNOPH w/ gd S.G.
" 88 " - 3'

Br. plug 5085

P/12 ~~5060-66~~ ~~Chen~~ ~~Ataku?~~
Swd N.S., Ac 500, Swd Id.

SEP 24 " + bail 6 gals water + 2
gals oil

Ac frac 5x5 Swd 1.7 BNO +
6.7 B. ac water - 4'
SQ w/ 275 SX

P/24 4590-4602

Swd. dry - N.S., Ac 1000
" Id., g. 3068 MCF (no water)
12' SIP 1105, ~~Intg~~

OCT 1 50 for repairs

OCT 8 repd. fld. 25.86 BNPH/81
2 1/2" ck SE inst Tank Bath

OCT 15 WOT 96.70 apkh for dual &

OCT 22 fld. 96.90 BO/8' $\frac{24}{64}$ " cb
Intg

OCT 29 IP flow 290 BNPH

Chen 5451-58 ~~4590-4602~~
phi @ ? ~~gas in tank is~~
SI

RE 5399 TD 5635

38° gty