



RTD 5750, logs (Sj) to 5754. 5½" @ 5430/250, MICT, CO

P 23/5347-53. swb 2 BOPH/90 mins.

627 P 86/5325-47. swb 1 BOPH/4 hrs. swb 20 BO/NT. 1000 Ac. swb ld. swb 2 BOPH/5 hrs. frac 15,000 gel oil x 15,000 sd swb pt ld. re-frac/10000 gel oil x 10,000 sd. swb pt ld/NS (lack 100 BL). SQ 5325-53/250 sx. CO 5332.

P 4 way jet @ 5328 & 5330. 600 Ac. frac 10000 gel oil X 10000 sd. SIP 950/14 hrs, flo 17 BL. swb 2½ BLPH/12 hrs. rec 900' FIH/12 hrs (lack 100 BL). 2000-15% Ac. 15,000-7½% Ac. rec ld. swb 1½ BGCOPH/NT. Swb 2 BL w/SSOPH/48 hrs. non-commercial.

D & A.

LIBERAL LOG TOPS

2944 KB

Winfield 2722 (+222)

Heebner 4100 (-1156)

Toronto 4125 (-1181)

Lansing 4190 (-1246) tst XW in "C" Zone

"D" Zone 4632 (-1688)

Marmaton 4772 (-1828)

Pay Zone 4798 (-1854)

Morrow 5204 (-2226)

"S-3" 5324 (-2380) 8/8; swb 2 BLW + SSOPH/48'

Chester 5358 (-2414)

Ste. Gen 5560 (-2414) 2556

St. Louis 5574 (-2630)

TD 5750