

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISS

OCT 29 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Walter Kuhn Drilling Company

Complete Address: 726-28 Union Center Bldg. Wichita, Kansas

Lease Name Masoner Well No. # 1

Location SW/4 Sw/4 Sec. 30 Twp. 28 Rge. 32 (E) (W)

County Haskell Total Depth 5389'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4 PM Day 26 Month 10 Year 63

The Above well was plugged as follows:

8 5/8"-2400' Circulated w/cement. 5 1/2"-5389' Cemented. Perforations-5325' to 5353'

Plug bottom w/15 Sax.cement 5389' to 5274' Mud 5274' to 2400'

Spotted 15 Sax.cement 2400' to 2285' Mud 2285' to 700'

Spotted 35 Sax.cement 700' to 600' Mud 600' to 50'

Rock bridge 50' to 40' 15 Sax.cement 40' to 0

Company Pump. Weld cap on surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/29/63
INV. NO. 4981-U