

90077

7-214 W + 78

MAP NO.

SEC. 32

TWP. 28S

RGE. 34W

STATE Kans COUNTY HaskellLOC. C SE NEOPERATOR Geo B. McClellan


FT. FROM _____ LINE

WELL NO. 1 FARM NAME McCoy

FT. FROM _____ LINE

CITY EubankELEV. 3011GR. 3018E. DF 3021 E. K.B.FR. 4/27/62 SPUD 5/9/62COMP. 7/24/62CONT. Co. tools /GEOL.

NAME PRODUCING INTERVAL	COMPLETION RECORD FROM — TO	PERF. W/HOLES	TREATMENT RECORD
a			
b			
c			
d			



I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	HRS.
b	"	"	"	"	"
c	"	"	"	"	"
d					

D & A

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBTD _____ TD 5560

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
<u>8 5/8"</u>	<u>@ 762</u>	<u>450</u>	<u>2 7/8"</u>	<u>@ 5510</u>	<u>130</u>
<u>4 1/2"</u>	<u>@ 4800</u>	<u>200</u>			

OPERATOR Geo B McClellan WELL NO. 1 McCoy ELEV. C SE NE

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums			Hb	4006	- 985
RTD (Sperg)	5560	-2539	Tor	4031	-1010
			Lans	4097	-1071
			KC"A"Zn	4585	-1564
			Marm	4706	-1685
			Morr	5177	-2156
			Chest	5355	-2334
			St. Gen	5431	-2410
			St. Lou	5473	-2452
			Sperg	5550	-2529
			LTD	N.A.	

DST #1 (No Top) 3940-50, Str pkr, Op 60", R 20' mud,
IBHP 1020#/NT, IFP 28#, FFP 28#, FBHP 1005#/NT.

DST #2 (Tor) 4074-92, Op 60", R 540' SW + 5' OCM, IBHP
1025#/NT, IFP 30#, FFP 230#, FBHP 940#/NT.

DST #3 (Lans) 4102-24, Op 1 hr., R 390' SW, IBHP 965#/NT.
IFP 45#, FFP 170#, FBHP 925#/NT.

DST #4 (Marm) 4709-25, Op 1 hr., R 90' OCM & 90' OCSW,
IBHP 1130#/20", IFP 0#, FFP 0#, FBHP 935#/20.

DST #5 (Morr) 5328-53, Op 1 hr., R 75' OCM, IBHP 1300#/NT.

IFP 0#, FFP 0#, FBHP 395#/NT.
RTD 5560, log, $4\frac{1}{2}$ " @ 4800 w/200 sx. PB 5504 /130 sx.
PETD 5504, ran cem dense log, A/500, perf 3/5463,
(Ste. Gen), swb ld, perf 20/5453-63 (Ste. Gen), A/500, swb
ld, swb 18 BO + 18 BAW/ $6\frac{1}{2}$ hrs, 28/5420-34 (Chest) Spot
30 gal salt gel 5453-63 to shut off, A/500 M + 2500
(15%) 5420-34, swb 3 BFPH, 50% wtr, NT, swb 20 BFPH (25%
oil) NT, SQ 5420-34, 20/5420-30 (Chest), A/500, (15%), swb 2
BFPH (25% oil), NT, PB 5380, 16/5330-38 (Morr) A/500 acid
(15%), Swb ld, Swb SSO, PB 4760, 4 way jet, 4707 (Marm) A/500,
(15%), swb ld, swb all water, D & A.

LIBERAL ELECTRIC LOG TOPS

3019 KB

Win ⁺³⁷³
Heebner 4014 (-975)
Toronto 4032 (-1013)
Lansing 4098 (-1079) XW
"D" Zone 4524 (-1505) tst OCM + OCXW
Marmaton 4674 (-1655) swb wtr ^{pay 2-1688}
Morrow 5176 (-2157)
Chester 5354 (-2335) swb 2 BFPH - 25% oil
Ste. Gen 5430 (-2411) swb 18 BO + 18 BZW/ $6\frac{1}{2}$ hrs)
St. Louis 5472 (-2463)
TD 5560 D & A.