

1-28-33W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SOUTHWESTERN EXPLORATION CO.
Farm- Anschutz No. 1

SEC. 1 T. 28 R. 33W
 C SW/4

Total Depth. 2810

Comm. 4-25-55

Comp. 4-30-55


Shot or Treated.

Contractor. Rocket Drilling Co., Inc.

Issued. 9-17-55

County Haskell

KANSAS



Elevation. 2964 RB

Production. 12,300,000 CFGPD

CASING:

8 5/8 552' w/ 400 sx cmt.
5 1/2 2810' w/ 250 sx cmt.

Figures Indicate Bottom of Formations.

sand & clay	40
sand	305
shale & shells	405
sand	490
shale	500
sand & shale	557
shale & shells	810
red shale	1050
red bed	1450
shale & sand	1700
shale & red bed	1905
lime & shale	2378
broken lime	2728
lime	2810
Total Depth	

TOPS:

Upper Krider	2695
Lower Krider	2722
Winfield	2771

MICT, C⁺ to 2801, Perf. 20/2790-92,
12/2749-52, Squeezed each zone w/ 200 sx cmt.
(shale breaks). CO & DC to 2787,
Perf. 60/2774-84, 34/2762-66, fair
show gas; Acid 1000 gals. gauged
500 MCFG, 12/20 gauged 659 MCFG plus
2 BWPH, SIP 420#, Wtr. decreased to 1/2
BWPH after 12 hrs. 36/20 gauged
1,500 MCFG, SIP 410#, 2000 gal. dolofrac,
300# press. 4/20 gauged 1,800 MCFG
plus 3 1/2 BFPH. LW plug @ 2747, Perf.
120/2720-40, small show gas, dolofrac
3000 gal, 1420# press. Drove plug to
btm. (2787') 72/20 gauged 11,300 MCFG,
w/ trace moisture, SIP 385#, 72/20
gauged 12,300 MCFG w/ trace moisture,
SIP 400#