

35 - 28 - 33W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
502 East Mydock, Wichita, Kansas

Company- NATIONAL ASSOCIATED
Farm- Jessie Jones No. 1

SEC. 35 T. 28 R. 33W
SW SW NE
100' NE of center

Total Depth. 2757
Comm. 11-12-50 Comp. 1-13-51
Shot or Treated.
Contractor. Walter Kuhn Drkg Co.
Issued. 1-26-52

County Haskell
KANSAS



CASING:

10 3/4" 680' cem w/350 sx. circ.
5 1/2" 2747' cem w/600 sx.

Elevation. 2956 and.

Production. 7,435,000 gas

Figures indicate Bottom of Formations.

surface clay	75
sand, yellow clay,	
gravel	240
clay yellow, sand	595
gravel	620
clay yellow, sand	635
shale blue	688
red bed, gyp	915
red rock, anhydrite	1305
red bed, sand	1435
shale, anhyd. strks	1665
red rock, shale, sand	
streaks & anhyd.	1960
shale, lime strks	2170
anhydrite, shale	2380
lime	2470
anhydrite, shale	2590
lime, dolo. strks	2655
shale	2730
lime	2757
Total Depth	

Tops: Scout.
Herington 2655
Krider 2681
Winfield 2732