

60' N & W of C SE SW

12-206W 18-77
 MAP NO. 3011Gr ELEV. 3021DF 3023KB
 STATE Kans COUNTY Haskell SEC. 33 TWP. 28S RGE. 34W
 OPERATOR Helmerich & Payne, Inc LOC. App C SE SW
 WELL NO. 3 FARM NAME Eubank "A" 720 FT. FROM S LINE
 Eubank 720 FT. FROM E LINE
 FR. 9/13/61 SPUD. 9/14/61 COMP. 12/20/61 SW/4

CONT./GEOL. Graham-Michaelis Drlg Tools

NAME PRODUCING INTERVAL		COMPLETION RECORD	PERF. W/HOLES	TREATMENT RECORD
FROM - TO				
Marm		4686-92	12	5500A

a				
b				
c				
d	P			

d I. P. OIL/DIST. 36BO WTR. 2BW GAS M.C.F.P.D. CHK. HRS. 24

b " " " " " "
 c " " " " " "
 d

SIP# FI TP # FI CP# SIBHP
 GOR. GR. 38.4 deg PSTD TD 4750

SIZE	DEPTH	CASING - CEMENT RECORD	SIZE	DEPTH	W/SAX.
8 5/8"	798	350			
5 1/2"	4749	400			

OPERATOR Helmerich & Payne WELL NO. 3 Eubank "A" ELEV. 3023KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB tops elev & datum					
Hb	3989		Hb	3989	- 966
Tor	4016	D Zone	Tor	4016	- 993
Lans	4074	4496-4475	Lans	4074	-1051
Marm	4599		Marm	4601	-1578
RTD (Marm)	4750 -1727		LTD	4750	-1727

DST #1 (Lans) 4495-4504, op 60", 240' GIP, R 15' oil + 45' HO&GCM, + 90' O&GCM + 90' SW, IBHP 1132#/30", IFP 28#, FFP 76#, FBHP 1004#/30".

DST #2(Marm) 4684-4700, op 1 hr, 3000 GIP, R 120' O + 120' V HO&GCM, IBHP 1220#/30", IFP 45#, FFP 100#, FBHP 1140#/30"

RTD 4750, log, 5 1/2" @ 4749 w/400 sx. MICT 12/4686-92 (Marm) no sho nat, 500MA, Swb 3 3/4 BOPH/NT, 5000 Jell A, Swb 1d, Swb 48 BO + 20% wtr/5 HRS, Gr 38 Deg, PB 4555, 8/4498-4502 (Lans) Swb 25 GFWPH w/scm oil, 500A. \$ 5 BFPH, 90%SW, Sq 4498-4502 50 sx, 20/4316-21 (KC) 500A. \$ 5 BOPD(25%wtr) 400' OB, Pull plug @ 4555, 2 1/16" tbg, w/Model "D" pkr @ 4675, 2 1/16" @ 4355, . State Pot: P 36 BOPD + 2 BOPD, Gr 38.4 deg. Marm 4686-92. P 21 B 1d O + 25 BSW/24 hrs, Abd KC Zn, Complete frm Marm only.

COMPLETED