
State Kansas ~~Fetmerrich + Payne Inc.~~ Field Eubank ✓
 Company White Eagle Oil Co. County Haskell
 Farm Eubank No. 1-A
 Sec. 33 Twp. 28S Range 34W

Spot C NW SW
 Contractor 5500'
 Remarks UP DHM

o		

Comm. 5/13/59 ? Comp. 8/4/59
 Elev. DF 3021 GL 3018 KB 3028 TD 5680 PB

Pay Chgs 5402-5460
 ? (non-prod) 5478-84 open gr 38.50

I.P. P 174 BOPD Press.
 Casing Record: 13 3/8 7"
 20" 10 3/4 5 1/2" 5540/500
 16" 8 5/8 812/500

LOCATION	Sample	UP Log
MAY 13 RU RT <u>Mrm Lan</u>	4117	
MAY 20 sp csg 4 3313 ⁴⁶²²	<u>Chero 4794</u>	Mar ⁻²¹⁵⁹ 5180
MAY 27 OST 4118-40	Mar	5187 ⁻²³⁷⁰ 5396
op 30 min wb b/p	Ch ^{82'} 5420	5429
stuck tool, fishing	36	Ch ⁻²⁴³¹ 5452
JUN 3 rec fish 41145	55 5452	5455 ^(20') -72
JUN 10 DST 4120-65	75	15 par ⁻²⁴⁵⁵ 5476
op lhr. rec 95' oct + sgcu		96 ^(10')
15IP 910/30"		Mb-891 3912
FP 50		Top ⁻⁹⁰⁹ 3930
FSIP 250/30"		lan ⁻⁹⁴¹ 3962
DST 4698-4731	Wh Eagle	B/KC 4076
op 30" rec 60' socm	Tops	Mrm bro 4536
+ 30' ocm 15IP 611/30"		Chero 4799
FP 42-63 FSIP 1105/30		White Eagle
05226		
JUN 17 OST 5390-5450		Mar ⁻²¹⁶³ 5194
op lhr. gts 10" (no gauge) rec		Ch ⁻²³⁷² 5393
4,120' free oil + 630' hot gcm		37' 5430
15IP 1530/30 FP 1005-1175		53 5449
FSIP 1505/30	CSO	25' 73
05480	Lsg 4100 (-1074)	St. G ⁻²⁴⁵⁶ 5477
DST 5456-85		86 ⁻²⁵²⁹
over		st. L. 5550

3028
2163
5191

Log A

Mrm

Mb SL
53

DST 5455-85 q/hr. gts 12"
 tstm rec 1080' oil (36 gr) + 600'
 40 x 90m 15IP 1460/60" FP
 65-225 175IP 1380/60
 RTD 5680 ring log. case WOC.

JUN 24 MICT → JUL 1 P 16/5452-60
 sub 64.17 80/6hr plug P 20/5402-12
 P 16/5420-29 ring T sub.

P 12/5478-84 580 A/1000 sub fd.
 sub 9.39 BOPH / 9hr. pl @ 5470 (10 BOPH)
 Com^{15.88} w/ Chester.

JUL 8 set plug 5440 Tub. KO fld 18 BOP/1hr.
 1 1/2" ck later F 12 BOPH 1/2" ck
 F 122 80/12hr. 1/2" ck + died 18 BOP/1 1/2" ck
 POP

JUL 15 : JUL 22 : JUL 29 - AUG 5
 1P P. 17.9 BOPD no uti
 q 38.5°
 Ches ~~5478-84~~ 5478-84 } open but
 5452-60 } non-prod.
 5420-29
 5402-12

178 BOPD is
 Capacity of Pump, not of well, should be bigger pot.

Order of perforations

Chsd { 5478-87 Az sub 9.39 BOPH } white Eagle says
 Plug 5470 } this oil coming
 5452-60 sub 10.9 BOPH/6 } from 5452-60 zone
 } even tho not open }
 drove out plug
 sub 9.4 BOPH/6 Both zones
 No plug
 No sd 5420-28 and 5402-12 NO Az or FA

Complicated for 178 BOPD.

H-P #1-A Eubank, C NW SW,
33-28S-34W, Haskell Co., Kansas

AMARILLO TOPS

3023 KB 2650 + 378
Winfield 2587 (+436)
Heebner 4014 (-991) .02
Lansing 4098 (-1075) T SGO&W
Marmaton 4682 (-1659) T SSO
Atoka 4975 (-1952) Pay 4714 - 1684
Morrow 5186 (-2163) T 245', Tss
36'
"S-3" 5390 (-2367) 26/36 /
Chester 5431 (-2408) / 174 BC
"C-2" 5449 (-2426) 21/22 / PD
por lm 5476 (-2453) swb 9.4
BOPH (comm ?)
St. Gen 5501 (-2478)
St. Luis 5582 (-2559)

5460-82