

A-9-20

MAP NO.

STATE Kansas COUNTY Haskell SEC. 33

3031 KB

ELEV. 3029 DF, 3017 GLOPERATOR Helmerick & Payne, Inc.-Garden CityTwp 28S Rge 34WWELL NO. 4 FARM NAME Eubank "D"LOC. C NW NETOL Eubank (PD 5600)


FT. FROM _____ LINE

FR. 6-5-61 SPUD 6-30-61 COMP. 8-21-61

FT. FROM _____ LINE

CONT./GEOL. Company Tools.

NAME PRODUCING INTERVAL		COMPLETION RECORD		TREATMENT RECORD
FROM	TO	PERF. W/HOLES		
a. <u>Chester</u>	<u>5465-90</u>	<u>36</u>	<u>1000Ac, F/20X20</u>	
b. _____	_____	_____	_____	
c. _____	_____	_____	_____	
d. _____	_____	_____	_____	



d. I. P. OIL/DIST. IP P 114 BOPD WTR. 2% GAS _____ M.C.F.P.D. _____ CHK. P HRS. 24

b. " " " " " " " "

c. " " " " " " " "

d. _____

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. 38° PBDT _____ TD 5640

CASING - CEMENT RECORD		SIZE	DEPTH	W/SAX.
a. <u>8-5/8"</u>	<u>713</u>	<u>350</u>	_____	_____
b. <u>5-1/2"</u>	<u>5580</u>	<u>600</u>	_____	_____

OPERATOR Helmerick & Payne, Inc. WELL NO. #4 Eubank "D" ELEV. 3031 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Topeka	3564	
			Heebner	4041	
			Toronto	4066	
			Lansing	4139	
			Marmaton	4649	
			Cherokee	4823	
			Morrow	5218	
			Chester	5465	
			St Louis	5508	

Spud 6-30-61. 8-5/8" @ 713 w/350 sx.

RTD 5640, logs (Sj). 5-1/2" @ 5580 w/600 sx. MICT.

9/24/5478-90, 12/5465-71, bld 30 GOPH/NT, 500 MA / 500-15% Ac,
 bld 39 GOPH/NT, Frac 20,000 Oil X 20,000 sd. Swb 410 BL/10
 hrs. Swb 234 BL / 116 BNO/3 hrs. 2" tbg @ 5468. Swb-would
 not flow.

POP

Pmp 154 BO / trace Wtr/24 hrs, Gty 38°.

IP Pump 114 BO / (2% Wtr)/24 hrs, Gty 38°, 54" Stroke, 12 SPM,
 from Chester (5465-90).

COMPLETE 8-21-61.

LIBERAL LOG TOPS

3031 KB

Winfield 2671 (+360)

Heebner 4044 (-1013)

Toronto 4064 (-1033)

Lansing 4138 (-1107)

"D" Zone 4546 (-1515)

Marmaton 4706 (-1675)

Pay Zone 4730 (-1699)

Morrow 5222 (-2191) T 272'; sd 24'

"S-3" Sand 5464 (-2433) ϕ pmp 144 BO + 2% wtr/24 hrs; 22/24

Chester 5494 (-2463)

Ste. Gen 5542 (-2511)

St. Louis 5626 (-2595)

TD 5640