

K-78 90078

State Kansas Field Eubank
 Company Helmerich & Payne County Haskell
 Farm Eubank USA "D" No. 1
 Sec. 33 Twp. 28S Range 34W
 Spot C NW SE
 Contractor Co. Tools 5600' :Miss
 Remarks



Comm. 8/15/59 Comp. 2/10/60
 Elev. Lts. DF 3018 GL KB 3019 TD 5604 PB
 Pay Ch. 5450-60

I.P. F 218.5 BOPD Press.
 Casing Record: 13 3/8 7"
 20" 10 3/4 5 1/2" 5510/650
 16" 8 5/8 789/500

LOCATION	Sample	Log
<u>AUG 1 9</u> sp csg. <u>φ 2384</u>		<u>Top 3527</u>
<u>AUG 9 6</u> DST <u>4095-4136</u>		<u>Hb 4010</u>
(Lap) <u>q 1 m. gts 30"</u>		<u>Tor 4037</u>
<u>totm rec 540' XW</u>		<u>Lgn ⁻¹⁰⁹⁰ 4108</u>
<u>ISIP 1205/60"</u>		<u>Mrm 4625</u>
<u>FP 203-311</u>		<u>Choro 4792</u>
<u>FSIP 1092/60"</u>		<u>Mor ⁻²¹⁵³ 5171</u>
<u>φ 4662</u>		<u>Ch ss ²³⁸⁰ 5415</u>
<u>SEP 2 3 Cores (no interval or closeup)</u>		<u>(12) 27</u>
<u>RTD 5604</u>		<u>ss ⁻²¹⁴⁰³ 5438</u>
<u>Aug</u>		<u>(32) 70</u>
<u>Est 5415-50 rec 35' total</u>		<u>St. L. ⁻²⁴⁴¹ 5476</u>
<u>11' ss brn-gg lite N.S.</u>		
<u>2' ss as ab. w/ chunks of sh.</u>		
<u>9' sh grn + rotten</u>		
<u>12' ss gy fn-med grain</u>		
<u>5' 444-49 bldg oil</u>		
<u>1' ss gol per bldg oil.</u>		
<u>Est 5450-74 rec 24'</u>		
<u>10' ss gol str 19% per</u>		
<u>oil sat 14-2072.</u>		
<u>14' ? ss + congl.</u>		
<u>(over)</u>		

E # 3 5475 - 5526 n 51'

1/2' sh blk

4 1/2' lm + chert

3' oöl lm

7' siltstone

36' oöl lm. N.S.

RTD 5604 Sj. CSG.

SEP 9 MILT CO P 40/5450-60

SEP 16 prep to tot.

A/500m subld & sub 9 BOPH

no wtr / 6' Fx 25 at X 25 sd.

flg / d.

SEP 23 3 day RD 9.5 A + 6 BOPH

pl @ 5000 P 80/4710-30 to ty

SEP 30 sub 9 BOPH due to 1 1/2 BOPH

no wtr / 12 hr CO 5460 32/4710-30

100 SX 200 ft / 20 BOPH

+ 36 no wtr to ty.

OCT 7 T 5431 sub KU F 6 BOPH + 56

ST WOT

OCT 14

OCT 21

OCT 28

NOV 4

NOV 11

NOV 18

NOV 25

DEC 2

DEC 9

DEC 16

DEC 23

DEC 30

JAN 13

JAN 20

JAN 27

FEB 3

Ch. F 144 BOPD 2 1/4" ch gas g. 4,115 mcf.

later F 4400 / 8 hr 2 1/4" ch gas g. 3,595 mcf

FEB 10

Ch. 5450-60 IPF 218.5 BOPD

no wtr 3 3/4" ch

LIBERAL TOPS

3019

Winfield 2644 (+365)

Toronto 4036 (-1017)

Lansing 4108 (-1089) gas & XW

Marmaton 4672 (-1653) 1 1/2 BOPH/12 hrs

Morrow 5174 (-2155) T 206', no sand

"S-3" 5414 (-2395) 8/14 Cone N & Chert

Chester 5427 (-2408)

sand 5438 (-2419) 26/30, 5 M + 6 BOPH 2 1/8 BOPD

St. Gen 5476 (-2467)

TD 5604

Ch sd 5414 - 2395 8/14 Cone N/S