

19-28-34W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY STANOLIND OIL & GAS

SEC. 19 T. 28 R. 34W

LOC. SW SW NE

150' N of SL & 150' E
of WL NE₄

FARM Flick Gas Unit NO. 1

COUNTY Haskell

KANSAS



TOTAL DEPTH 2825

COMM. 11-8-50

COMP. 11-14-50

SHOT OR TREATED

CONTRACTOR

ISSUED 1-13-51

CASING

10 3/4" 798' cem. w/440 sx.
7" 2805' cem. w/500 sx.

ELEVATION

3036 Ind.
3038

PRODUCTION 9,601,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

surface sand & clay 630
shale blue & sand 750
red bed 800
red bed, sand 1197
red bed, gyp 1610
gyp, anhyd. 1773
anhyd. 2170
shale 2198
shale, lime 2415
lime 2825
Total Depth

Tops:

Herington-Krider 2621
Winfield 2700
Towanda 2753
Ft. Riley 2805

Schlumberger ran to 2806

McCullough perf. w/6 SPF:

Herington-Krider 2626-2643
2680-2917
Winfield 2705-2714
2718-2730
Towanda 2758-2796

Acid:

Ft. Riley w/2500 gal. 15%, flushed
w/4500 gal. wtr.
Herington w/1500 gal. 15%, flushed
w/700 gal. wtr.
Krider w/1500 gal. 15%, flushed w/700
gal. wtr.
Winfield w/2500 gal. 15% flushed
w/700 gal. wtr.
Towanda w/300 gal. 15%, flushed
w/700 gal. wtr.
All zones w/12,000 gal. 7 1/2% flushed
w/4500 gal. wtr.

All zones w/8000 gal. 7 1/2% flushed w/4500
gal. wtr.
All zones w/4000 gal. 7 1/2% flushed
w/4500 gal. wtr.