


TKT 16821

1324

I



WESTERN TESTING CO. INC.
SUBSURFACE PRESSURE SURVEY

DATE: 6/22/83 TICKET #16821
CUSTOMER: VINCENT OIL CORPORATION LEASE: EUBANK
WELL: 1 TEST: 1 GEOLOGIST: PAUL HAGEMER
ELEVATION (KB): 1911 FORMATION: MISSISSIPPI
SECTION: 34 TOWNSHIP: 28S
RANGE: 12W COUNTY: PRATT STATE: KANSAS
GAUGE SN #13240 RANGE: 4500 CLOCK: 12

INTERVAL TEST FROM: 4254 FT TO: 4274 FT TOTAL DEPTH: 4274 FT
DEPTH OF SELECTIVE ZONE: FT
PACKER DEPTH: 4249 FT SIZE: 6 5/8 IN PACKER DEPTH: 4254 FT SIZE: 6 5/8 IN
PACKER DEPTH: FT SIZE: IN PACKER DEPTH: FT SIZE: IN

DRILLING CONTRACTOR: WHEATSTATE
MUD TYPE: DRISPAC VISCOSITY: 42
WEIGHT: 9.4 WATER LOSS (CC): 12.4
CHLORIDES (P.P.M.): 16000

JARS - MAKE: SERIAL NUMBER:
DID WELL FLOW? YES REVERSED OUT? NO
DRILL COLLAR LENGTH: 120 FT I.D.: 2.7 IN
WEIGHT PIPE LENGTH: FT I.D.: IN
DRILL PIPE LENGTH: 4111 FT I.D.: 3.8 IN
TEST TOOL LENGTH: 23 FT TOOL SIZE: 5 1/2 OD IN
ANCHOR LENGTH: 20 FT SIZE: 5 1/2 OD IN
SURFACE CHOKE SIZE: 3/4 IN BOTTOM CHOKE SIZE: 3/4 IN
MAIN HOLE SIZE: 7 7/8 IN TOOL JOINT SIZE: 4 1/2 XH IN

BLOW: STRONG.
GAS TO SURFACE IN 1 MINUTE.
SEE ATTACHED GAS SHEET.

RECOVERED: 1 FT OF: DISTILLATE
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:

REMARKS:

TIME SET PACKER(S): 5:15 PM
WELL TEMPERATURE: 128 °F
INITIAL HYDROSTATIC PRESSURE:
INITIAL FLOW PERIOD MIN: 15
INITIAL CLOSED IN PERIOD MIN: 63
FINAL FLOW PERIOD MIN: 30
FINAL CLOSED IN PERIOD MIN: 75
FINAL HYDROSTATIC PRESSURE

TIME STARTED OFF BOTTOM: 8:15 PM
(A) 2155 PSI
(B) 1217 PSI TO (C) 1222 PSI
(D) 1435 PSI
(E) 1205 PSI TO (F) 1226 PSI
(G) 1435 PSI
(H) 2094 PSI

WESTERN TESTING CO. INC.
GAS FLOW REPORT

DATE: 6/22/83

TICKET #16821

CUSTOMER: VINCENT OIL CORPORATION

LEASE: EUBANK

WELL: 1

TEST: 1

GEOLOGIST: PAUL HAGEMER

ELEVATION (KB): 1911

FORMATION: MISSISSIPPI

SECTION: 34

TOWNSHIP: 28S

RANGE: 12W

COUNTY: PRATT

STATE: KANSAS

GAUGE SN #13240

RANGE: 4500

CLOCK: 12

TIME GAUGE (MIN)	TESTER TYPE	ORIFICE SIZE	PRESSURE (PSI)	FLOW DESCRIPTION
---------------------	-------------	-----------------	-------------------	------------------

PRE FLOW

5:16 PM

GAS TO SURFACE

5	MERLA	2	40 PSIG	5210000 CFPD
---	-------	---	---------	--------------

10		2	45 PSIG	5690000 CFPD
----	--	---	---------	--------------

SECOND FLOW

6:30 PM

TOOL OPEN

5	MERLA	2	36 PSIG	4830000 CFPD
---	-------	---	---------	--------------

15		2	45 PSIG	5690000
----	--	---	---------	---------

25		2	45 PSIG	5690000 CFPD
----	--	---	---------	--------------

GAS BOTTLE SN #: 101

DATE BOTTLE FILLED: 6/22/83

DATE TO BE INVOICED: 6/26/83