

MAP NO. _____

ELEV. 3014 DF

STATE Kans. COUNTY Haskell SEC. 34 TWP. 28S RGE. 34W

OPERATOR Helmerich & Payne LOC. C NW SW

WELL NO. 1 FARM NAME Gregg FT. FROM _____ LINE _____

STATION	DATE	TIME	REMARKS	FT. FROM	LINE
Eubank					

5-25-60 SPIID 5-21-60 COMP 9-27-60

CONT./GEOL.Co. Tools

COMPLETION RECORD

COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM — TO	PERF. W/HOLES	TREATMENT RECORD

Marm	4698-4706	16	Nat
------	-----------	----	-----

c _____

d. _____

d. I. P. OIL/DIST. 47 BO WTR. 10 BW GAS 0 M.C.F.P.D. 0 CHK 0 HRS. 24

b " " " " " "

" " " " " "

D & A (

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. 34.7° PBD 5300 TD 5598

Casing - Cement		Record	
Size	Depth	Size	Depth

DEPTH	W/300	SIZE	DEPTH	W/300
10 3/4"	769	500		

7" 5406

OPERATOR Helmerich & Payne WELL NO. 1 Gregg ELEV. 3014 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
-------------	-------	---------	------------	-------	---------

Heeb 4006 Tor 4030

Tor	4029	Lans	4105
-----	------	------	------

Lans	4102	Marm	4616
------	------	------	------

Marm	4614	Chero	4773
------	------	-------	------

Morr 5148

#1 DST 4091-4130 (Tor-Lans) Lm 5209-26 SO

0 1 hr. R gas/1" Sd 5289-5300 SO

3/4 Mcfg/7" 190' GCM Chest Sd 5336-46

IFP 443# FFP 223# St. Gen 5406

FBHP 1182# /1 hr St. Lou 5460

#2 DST 4680-4700 (Marm)

0 1 hr. gas/12" TSTM 360' oil 90' HO&GCM IFP 56#

FFP 140# IBHP 1348# FBHP 1320#/60" RTD 5598 7" 5406

Pf 14/5209-15 Plug 4754 Pf 16/4698-4706 Pkr @ 5150

CO 5300 PBTD Prod Pkr @ 5200 1" tbg @ 5204 2" tbg @

4700 P 40 BO + 25% Wtr Marm (4698-4706) F 7 BOPD

w/SS gas Marm (5209-15) to rework (May not rework

until January) SI

IPP P 47 BO + 10 BWPD Gr. 34.7° COMPLETE

COMPLETE

COMPLETE
See other ticket

LIBERAL TOPS

3016 KB

Winfield 2644 (+372)

Heebner 4012 (-996)

Toronto 4028 (-1012)

Lansing 4102 (-1086) *T go*

Marmaton 4614 (-1598)

Morrow 5150 (-2134) T 202', Tss 30'

Ls 5208 (-2192)

sdv 5286 (-2270) ?10/18

sdv 5334 (-2318) ?10/12

Chester 5352 (-2336)

St. Gen 5404 (-2388)

St. Louis 5458 (-2442)

TD 5598

Corr 4664 - 1648

Page 2 - 1678 f

D Zone 4516 - 1506 8' wet?