

2-30W MAP NO. 2-79 SEC. 36-28S-39W
STATE Kans COUNTY Stanton LOC. C NE SW
OPER. Sinclair Oil & Gas Co. - Wichita, Ks. FT/FR _____ LINE _____
WELL 2 FARM Fred Shore Unit (WN) 2-5 FT/FR _____ LINE _____
Panoma Gas Area ELEV. 3135 GR. 3140 DF. 3143 KB
CONT. E.F. Wakefield Drlg. GEOL. Coy Dowty
CO. _____
INT. _____

F.R. 11-30-64 SPUD 11-29-64 COMP. 2-4-65
TD. 3044 FM. B/CG PBTD. _____
CG 2582-2780 196 2000A & Frac

COMP. RECORD
OF: Ga 4,750,000 Cfgpd (No Press)
8" @592 w/550 sx. 4½" @3042 w/400 sx.



Data Inc.

(GR Log) No WLT's, No DST's, RTD 3042, Sj Log
C, Anh 1625 / 1518 @3044, 4½" @3042 w/400 sx. (Lost Circ
Herr 2288 / 855 @3042), Temp Survey showed no cem behind
CG ~~2578~~ / 565 pipe, re cem, GRN Log to 3010, Pf 4/2915-
B/CG 2848 / 295 2916 (CG), Sq w/250 sx., Temp Survey
LTD 3044 / 99 2874, Top cem 2825, Pf 4/2823-24 (CG), Sq
RTD 3042 / 101 w/100 sx., Re Sq w/200 sx., Pf 4/2660-61,
Ret @2640, Sq w/40 in 2660-61, Rev out
13 sx., Temp Survey, top cem @2530, CO (no depth), Pf 56/2582-96,
2632-40, 16/2644-48, 32/2711-19, 28/2742-49, 32/2772-80 (CG),

\$ 34 BLW w/160,000 Cfgpd, 2000A & 125 sealers (ld -99 B), \$ 60
BL&AW/7 hrs, \$ 1½ BLAW/PH/3 hrs & est 324,000 Cfgpd, Gell wtr
Frac w/150,000 Gell wtr x 75,000# sd (Ld -3344 B), SI/5 hrs, \$
120 BLW/7 hrs, \$ from 2200' (FL 1900') (-3124 GL), \$ & flo 773
BLW/24 hrs, Last 4 hrs Flo 84 BLW & est 6,140,000 Cfgpd thru
4½" csg, Flo 120 BLW/20 hrs, last hr Flo 542,000 Cfgpd & tr LW thru
4½" csg (-2231 Gal LW), OF Ga 4,750,000 Cfgpd, no press, CG
2582-2780 - COMPLETED (1-29-65)

CSC EL Log

W 2380 + 755
CGro 2620 + 515