


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CLAY BROS.
Henthorne No. 1

SEC. 15 T. 28 R. 37W.
SW SE NW

Total Depth. 2630
Comm. 3-26-41 Comp. 4-17-41
Shot or Treated. 9000 gal acid.
Contractor.
Issued. 5-10-41

County Grant



CASING.

103/4" 543'
7" 2376'

Elevation.

Production. 9,645,000 GAS.
R.P. 415#

Figures Indicate Bottom of Formations.

Calechi and shell	65
shale and sand	195
shale, sand gravel & shell	376
shale sand and red bed	552
red bed and shell	715
red bed	770
red bed and gyp	958
red bed and shell	1144
red bed, gyp and shells	1198
gyp and red bed	1235
red bed, sand and gyp	1488
red bed, strks anhydrite	1660
red bed and gyp	1724
anhydrite	1735
anhydrite red bed and shells	1833
red bed and anhydrite	1910
red bed and shells	1966
shale and shells	2040
red bed and anhydrite	2118
red rock, anhydrite and shale	2190
shale lime and anhydrite	2254
anhydrite and red bed	2287
anhydrite shale and red bed	2360
shale anhydrite and lime	2401
dolomite	2406
sand gas	2407
sand gas	2410
lime grey	2420
lime	2425
shale red and blue	2436
lime	2480
shale brown	2500
lime grey	2530
sd lime	2545
lime grey	2590
lime hard	2600
lime grey	2620
lime grey hard	2625
shale red	2630
Total Depth.	

show of gas 2407