

17-28-39W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - STANOLIND OIL AND GAS COMPANY
Farm - Horner Gas Unit No. 1

SEC. 17 T. 28 R. 39W
SWc NE
2490' NSL & 2490' WEL NE/4

Total Depth. 2470'
Comm. 10-20-47 Comp. 11-17-47
Shot or Treated. Acidized
Contractor.
Issued. 1-24-48

County. Stanton
KANSAS



CASING:
10 3/4" 639' cem. 325 sx.
7" 2268' cem. 350 sx.

Elevation. 3186 ft.

Production. 1,690,000 Gas 20
min open flow

Figures indicate Bottom of Formations.

clay, sand	300
sand & clay	555
sandy lime	590
red bed	640
redbed & anhydrite	1670
redrock, anhydrite and lime	2135
redrock, lime and shale	2275 RTD
shale	2290
lime, sand, redrock, shale	2350
lime, sand & redrock	2415
sand lime	2470
Total Depth.	

Schlumberger ran to 2461'

TOPS:

Herrington-Krider	2268-2302
Winfield	2322-2349
Towanda	2374-2410
Ft. Riley	2431-2470

Acidization

All zones AW 2000 gal 15%, Displaced.
Max press 500#. Broke to 100#. Time 20
min. All zones REAW 14,000 gal 15%, 11,000
gal flush, 6 pump trucks max press 200#.
Broke to 50#. pumping time, Acid 13 min.
Water 11 min.