


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **PAN AMERICAN PETROLEUM CORP.**
 Farm- **Glenn Gas Unit "B" No. 1**

SEC. 8 T. 28 R. 39W
C NE SW

Total Depth. **5850'**
 Comm. **4-5-61** Comp. **4-26-61**
 Shot or Treated.
 Contractor. **Herndon Drlg.**
 Issued. **8-5-61**

County **Stanton**
KANSAS



CASING:
10 3/4" 693' cem w/600 sx.

Elevation. **3192' Gr.**

Production. **Dry**

Figures Indicate Bottom of Formations.

surface	670
sand	693
shale-red bed	1260
redbed - salt - shells	1590
Anhydrite	1645
shale - Anhydrite	1860
shale - shells	2110
lime - shale	2780
lime	2990
lime, chalk	4645
lime	4953
lime - shale	5107
shale	5382
lime	5443
sand - lime	5475
lime - shale	5583
lime - sand	5635
lime - shale	5683
lime - chert	5690
Anhydrite - gyp - lime	5735
lime - Anhydrite	5763
lime	5850
Total Depth	

TOPS: SCOUT	
Council Grove	2554
Pennsylvanian	2992
Missourian	3792
Des Moines	4402
Morrow	5073
Morrow Sand	5150
Morrow Marker	5316
Morrow Sand	5354
St. Genevieve	5414
St. Louis	5486