

10-273W

MAP NO.

K-78

SEC. 4-28S-34W

STATE

Kans

COUNTY

Haskell

LOC.

C SW SE

OPER. Cities Service Oil Co. - Liberal, Kansas

FT/FR

LINE

WELL 1 FARM Cooper "F"

FT/FR

LINE

Eubank North ELEV. 3070 GR. 3081 DF. 3084 KB

CONT. R.W. Rine GEOL. Bill Jacques

CO. 5450' Miss Test

F.R. 8-24-64 SPUD. 8-26-64 COMP. 10-27-64

TD. 5470 FM. Chester PBTD. 5438

Morrow 5382-5428 56 250A

State Pot: P 133 BOPD & 1% wtr (Gr 36.8 deg)

8 5/8" @1870 w/500 sx. 4 1/2" @5470 w/110 sx.

(KB Log) DST #1 (Lans-A) 4179-4200, Op 1 hr, R

Hb 4032 - 948 1885' Sli sul wtr & 270' salty mud, ISIP

Tor 4046 - 962 not taken, IFP 131#, FFP 767#, FSIP

Lan 4128 -1044 877#/30"

Lan-D 4542 -1458 DST #2 (Mrw) 5362-85, Op 1 hr, GTS/6",

Marm 4706 -1622 TSTM, R 5000' gsy oil, No ISIP, IFP 548#,

Marm pay 4732 -1648 FFP 1158#, FSIP 1191#/30", RTD 5470, Log,

Mrw 5222 -2138 4 1/2" @5470 w/110 sx., CO 5438, Perf 24/

Mrw sd 5359 -2275 5422-28 (Mrw), \$ tr oil - nat, 250A (15%),

ont Below) \$ 1d, \$ 135 BO & 13 Bbls of BS&W/10 1/2 hrs,

B/Mrw sd 5374 -2290 PB 5413, Perf 32/5382-90 (Mrw), \$ 158 BO &

Mrw sd 5378 -2294 1/2 Bbls of BS&W/7 hrs, CO 5438 PBTD, \$ 104

B/Mrw sd 5390 -2306 BO & 13 BW/8 1/2 hrs, Gr 36.8 deg., GOR 837-


Mrw sd 5418 -2334 1, Est \$ 294 BOPD - POP

B/Mrw sd 5425 -2341 State Pot: P 133 BOPD & 1% wtr, Gr 36.8

Ches 5431 -2347 deg., Mrw 5382-5428 - COMPLETED (10-16-64)

LTD 5470 -2386

RTD 5470



Data Inc.