

A-4-212

MAP NO. 12-78

ELEV. 3090 KB

ELEV. 3083 GL

STATE Kansas COUNTY Haskell SEC. 4 Twp. 28 S Rge 34 W

OPERATOR R. W. Rine Drilling Co. - Wichita, Kans LOC. C NE NE

WELL NO. 1 FARM NAME Bell "B" FT. FROM _____ LINE _____

DOL. Eubank, No (PD 5750) FT. FROM _____ LINE _____

FR. 3-8-61 SPUD 3-9-61 COMP. 3-31-61

CONT./GEOL. Company tools

COMPLETION RECORD
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a			
b			
c			
d			

a I. P. OIL/DIST. _____ WTR. _____ GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. _____

b " " " " " " " " " "

c " " " " " " " " " "

d _____

D & A

D & A (X)

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT _____ TD 5580

CASING - CEMENT RECORD
 SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
8-5/8" 1850 650 _____ _____ _____ _____

OPERATOR R. W. Rine Drilling WELL NO. 1 Bell "B"

ELEV. 3090 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Heebner	4031		Council Grove	3110	
Toronto	4046		Heebner	4028	
Lansing	4138		Toronto	4043	
Marmaton Lime	4708		Lansing	4126	
			Marmaton	4682	
			Cherokee	4812	
			Morrow	5170	
			Morrow Sand	5303	
			Ste Genevieve	5418	
			St Louis	5510	

Spud 3-9-61. 8-5/8" @ 1850 w/650 sx.

DST # 1 (Kri) 2942-66, op 1 hr, rec 105' M, ISIP 440/30 mins, FP 40-55, FSIP 355/30 mins.

DST # 2 (CG) 3197-3242, op 2 hrs, wk blo, rec 630' M/NS, ISIP 635/30 mins, FP 325-330, FSIP 485/30 mins.

DST # 3 (Lans) 4553-70, op 1 hr, rec 180' VSGCSW, ISIP 1247/30 mins, FP 42-84, FSIP 1075/30 mins.

DST # 4 (Marm) 4703-20, op 1 hr, GTS 4 mins, TSTM, rec 145' GCM + 85' GCSW, ISIP 1242/30 mins, FP 102-144, FSIP 1095/30 mins.

Shake
DST #5 (Mor) 5323-41, op 1 hr, rec 2' M, pressure not avail.

DST #6 (Mor) 5344-94, op 1 hr, rec 10' M, ISIP 105/30 mins,
FP 25-25, FSIP 40/30 mins.

@ 5394 ran logs.

DST #7 (Lans) 4125-28 (SP), op 1 hr, rec 320' GCM + 825' GCXW,
ISIP 1060/30 mins, FP 160-605, FSIP 935/30 mins.

RTD 5580, logs to 5580.

D & A.

90 - use
3085 KB - ?

LIBERAL TOPS

Win 2700 +390

C. G. 3110 (-29) T mud

Heebner 4028 (-943)

Toronto 4044 (-954)

Lansing 4126 (-1041) T. GCM. XW

"D" Zone 4536 (-1451) T vs GCXW

Marmaton 4682 (-1597) TG + W

Morrow 5174 (-2089)

"S-3" 5324 (-2239) 6/11 T 21 M

"S-3" 5348 (-2263) 2/6 T 10' M

Chester 5354 (-2269)

St. Gen 5440 (-2355)

St. Louis 5522 (-2437)

TD 5586

norm pay 4706 - 1616 = 664w