

4-208W

MAP NO.

2-78

OWWO

SEC.

4-28S-34W

STATE Kans

COUNTY Haskell

LOC

C NE NE

OPER R.W. Rine Drlg. Co. - Wichita, Ks.

FT/FR LINE

WELL 1 FARM Bell "B"

FT/FR LINE

Eubank North (Mrw & Miss O/G) EV. 3083 GR.

DF 3090 KB

Co. tools - Rig #3

GEOL. Paul Harper

INT. Cities Service Petr - Farmout

F.R. 2-26-65

SPUD

3-9-61

COMP.


4-22-65

TD. 5587

FM. St L

PBD.

D&A



COMP. RECORD

8" @1850 w/650 sx.

5 1/2" @5486 w/150 sx.

Data Inc.

(Old KB Log)

OLD INFO: (Same Operator)

No upper tops called

DST #1 (Kri) 2947-66, Op 1 hr, R 105' M,

CG 3110 - 20

ISIP 440#/30", IFP 40#, FFP 55#, FSIP

Hb 4028 - 938

355#/30"

Tor 4043 - 953

DST #2 (CG) 3197-3242, Op 2 hrs, WB-died/

Lans 4126 -1036

20", incr to FB/45", R 630' M, No O/G or

Marm 4682 -1592

wtr, ISIP 635#/30", IFP 325#, FFP 330#,

Chero 4812 -1722

FSIP 485#/30"

Mrw 5170 -2080

DST #3 (Lans) 4553-70, Op 1 hr, FB, R

ont Below)

180' VSGCSW, ISIP 1247#/30", IFP 42#,

Mrw sd 5303 -2213

FFP 84#, FSIP 1075#/30"

Ste G 5418 -2328

DST #4 (Marm) 4703-20, Op 1 hr, SB, GTS/

St L 5510 -2420

4", dec in 30", TSTM/30", R 145' GCM &

LTD 5580 -2490

85' GCSW, ISIP 1242#/30", IFP 102#, FFP

(KB Spl)

144#, FSIP 1095#/30"

Hb 4031

DST #5 (Mrw) 5323-41, Op 1 hr, R 2' M,

Tor 4046

Press (?)

Lans 4138

DST #6 (Mrw) 5344-94, Op 1 hr, R 10' M,

BKc not called

ISIP 105#/30", IFP 25#, FFP25#, FSIP

Marm lm 4708

40#/30"

TD 5580 -2490

DST #7 (Lans) 4125-48 (Str Pkr) Op 1 hr,

DDTD 5587 -2497

R 320' GCM & 825' GCSW, ISIP 1060#/30",

IFP 160#, FFP 605#, FSIP 985#/30", RTD

80 in St L, D&A (3-31-61) - Completed

NEW INFO: MIRT 3-1-65, CO & DD 5587 New TD, Set 5 1/2" @5486 w/150

sx., LW Log to 5449, Pf 12/5327-5330, 120/5352-5382 (Mrw), NSO,

2000 MCA (ld 134 BLO & 48 BA), \$ on ld w/SSO, R 163 BL, No rec

all ld, Pf 9/5327-30, 9/5350-53 (Mrw), Frac 20,000# sd x 20,000

Viso-Frac & 120# Adomite per gal & 35 gal Hi Flo (Ld 650 Bbl), \$

to btm R 284 BL (-366 BL), FU 2700' F/1 week, \$ & Rec 28 BO & 29

BW (\$ 97% wtr/OB), D&A & Plugged March 1965 - COMPLETED (4-20-65)

See other Ticket X