


7-83W Map No. K-78  
OPER R.W. RINE DRLG. CO. - WICHITA, KS.



S-T-R 4-28S-34W  
SPOT Q NE SE  
CO HASKELL (KS)  
ELEV 3082 KB

WELL #1 COOPER  
FOR CO. TOOLS  
FIELD EUBANK NORTH (MRW & MISS)  
I.P. P 40 BOPD + 2 BWPD, MRW 5366-87 (GR 39)

(KB LOG)  
HB 4030 - 948  
TOR 4044 - 962  
LAN 4128 - 1046  
CHER 4860 - 1778  
MRW SH 5190 - 2108  
MRW SD 5336 - 2254  
MRW SD 5364 - 2282  
RTD 5450 - 2368  
LTD NA

SPUD 4-20-66 8" 1930 W/ 750 SX. PAUL HARPER - GEOL  
CITIES SERVICE OIL - FARMOUT  
DST #1 (MRW SD) 5335-80, OP 60", GTS/1 HR & 25", R 410'  
OIL & OCM, ISIP 933#/30", FP'S 86-202#, FSIP 904#/30"  
RTD 5450, LOG, 5" 5449 W/CEM  
MICT, CO PE 6/5384-87 (MRW), NTN, 500 MCA, § DN, §  
3/4 BFPH (50% O&M + 50% WTR), 1500 MCA, § APP 3/4 BFPH,  
FRAC 10,000 GAL VISSCO FRAC X 4200# SD, NO REC ALL LD,  
§ 10 BFPH, PB 5379, PF 20/5366-76 (MRW), NTN, 1500 MCA, §  
ON LD (-200 BL), § 3 1/3 BFPH, FU 30 BF/12 HRS, NO BD, FRAC  
20,000 GAL VISSCO FRAC X 9500# SD. § TO BTM, § 10 BFPH/  
10 HRS, LAST 6 HRS - ALL OIL, CO 5425 PBTD, POP, REC LD  
P 60 BOPD + GAS (NO GA) + WTR (GAS ENOUGH FOR LEASE WORK)  
CO P 40 BOPD + 2 BWPD, MRW 5366-87 (GR 39)  
COMPLETED (7-8-66)

*Data Inc*

MISCEL DATA  
GEOL PAUL HARPER ELEV 3079 DF SPUD DATE 4-20-66  
FTG 3072 GR DRLG COMP \_\_\_\_\_  
SUPPT CITIES SERVICE - SUPPORT FR by DATA 3-23-66  
CSG 8" 1930 W/750 SX. 5" 5449 W/CEM COMP by 7-14-66

3080DF

REVISED LIBERAL ELECTRIC LOG TOPS

3082 KB

Heebner 4030 (-948)

Toronto 4042 (-960)

Lansing 4128 (-1046)

"C" 4384 (-1302)

"D" 4546 (-1464)

Marmaton 4702 (-1620)

Morrow 5190 (-2108)

Limestone 5272 (-2190)

"S-3" "A" 5334 (-2252) 10/18

"B" 5364 (-2282) 20/22;  $\varnothing$  P 85 BOPD

Chester 5388 (-2306)

TD 5450

Mr. Bay 4722 - 1640 NT