

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- J. M. HUBER CORPORATION
Farm- Walkemeyer No. 1

SEC. 22 T. 28 R. 42W
CNE SW

Total Depth. 5770'
Comm. 7-10-54 Comp. 8-11-54
Shot or Treated.
Contractor. Big Chief Drlg. Co.
Issued. 12-13-54

County Stanton
KANSAS



CASING:
8 5/8" 1529' cem w/700 sx

Elevation. 3520' DF

Production. Dry

Figures indicate Bottom of Formations.

surface sand & shale	720
sand and red bed	925
shale and shells	1441
shale and anhydrite	1640
shale and shells	2489
shale	2740
lime	3071
sandy shale	3129
shale and lime	3270
lime	3443
sandy lime	3510
lime	3770
lime and shale	3815
cherty lime and shale	3936
lime	4689
cherty lime	4725
lime	5030
lime and shale	5088
shale	5560
sand	5570
lime	5770
Total Depth	

Tops:

Cimarron Anhydrite	1673
Base Cimarron Anhy.	1705
Krider	2693
Winfield	2730
Towanda	2788
Topeka	3268
Lansing	3804
Marmaton	4274
Cherokee	4520
Morrow Shale	5122
Morrow Lime	5430
Keyes Sand	5546
Miss. (St. Gen.)	5558
Miss. (St. Louis)	5760

Schlumberger total depth 5768'

DRILL STEM TEST:

3515-35, open 1 hr., rec. 305' salt water,
FP 0-150#. 15 min. SIBHP 615#.

3740-3770, open 1 hr., Rec. 250' muddy
salt water, RP 0-130#, 15 min. SIBHP 640#.

4344-60, open 1 hr., Rec. 15' mud, FP 0-0#,
15 min. SIBHP 375#.

5550-5570, open 1 hr., Rec. 1020' salt water,
FP 0-400#, 20 min. SIBHP 855#.

5562-5650, open 1 hr., Rec. 15' drilling
mud, FP 0-0#, 20 min. SIBHP 270#.

Straddle test, 3948-4014, open 1 hr., Rec.
5' mud, FP 0-0#, 15 min. SIBHP 615#.