

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock,
Wichita, Kansas


30-28-5W

Company- DRILLER'S PRODUCTION CO.
Farm- Kostner No. 2

SEC. 30 T. 28 R.5W
NW SE NE

Total Depth. 4678'
Comm. 7-9-61 Comp. 7-30-61
Shot or Treated.
Contractor. Gabbert-Jones Drlg. Co.
Issued. 11-25-61

County Kingman
KANSAS



Elevation. 1434' KB

CASING:
10 3/4" 263' cem w/225 sx.
7" 4445' cem w/200 sx.

Production. SWDW

Figures Indicate Bottom of Formations.

red rock, shale & shells 125
shale & shells 263
shale & shells 760
Anhydrite 785
lime & shale 1225
lime 1545
lime & shale 2750
sandy shale 2875
sandy shale w/lime 3020
lime & shale 3213
lime 3350
lime & shale 3855
lime 3867
cherty lime 3899
lime 3950
lime & shale 4045
lime w/chert 4066
lime 4215
chalky lime & shale 4240
lime & shale 4299
sand & shale 4333
lime & shale 4345
sandy lime & shale 4386
shale & lime 4423
dolomite 4445
dolomite & lime 4465
lime 4636
lime w/dolomite 4674
lime 4678
Total Depth

DST 3870-85', op 1 hr, G/45", 35 MCFD,
Rec. 60' GCM, IFFP 25-33#, I-FCIP/30",
1340-1268#.

DST 3884-99', op 1 hr, G/ 20", 50 MCFD,
Rec. 40' O & GCM, 30' GCM, 30' wtry M,
50' ndy wtr. I-FFP 69-74#, I-FCIP/30"
1403-1238#.

Perf: 25/S 3885-91'

Perf: 16/S 3884-88' 300 gal. mud acid.

TOPS:
Heebner 2790
Brown Lime 3021
Lansing 3094
Mississippi 3855
Kinderhook 4144
Viola 4258
Simpson Dolomite 4279
Simpson Sand 4298
Arbuckle 4397