

10-251W Map No. K-78


OPER CITIES SERVICE OIL CO. - Liberal,  
Ks.

WELL #1 PILAND "A"

CO Rine Drlg.

FIELD Eubank N (Mrw-Miss) Field

I.P. \_\_\_\_\_



S-T-R 5-28S-34W  
 SPOT C SW SE  
 CO HASKELL (Ks)  
 ELEV 3083 KB

(KB Log)

Hb 4058 - 975  
 Tor 4072 - 989  
 Lan 4152 - 1069  
 "D" zn 4578 - 1495  
 Mar 4734 - 1651  
 Pay zn 4768 - 1685  
 Mrw 5230 - 2147  
 Mrw lm 5314 - 2231  
 Mrw sd 5380 - 2297  
 B/sd 5390 - 2307  
 Chest 5440 - 2357  
 Ste G 5514 - 2431  
 LTD 5550 - 2467

RTD 5550, Log, 4" @5448 w/110 sx.

MICT, CO 5416 PBTB, 1d hole w/15 BW, Pf 40/5398-  
5408 (Mrw sd), § dry-NS, 500A & 88 B treated wtr, Max P  
 1650#, § 95 BLW/10 hrs, had SO last 3 hrs, SI/12 hrs, §  
 75 Gal wtr & scum oil/last 2 hrs of 9 hr test, Frac 5000  
 gal crude x 5000# sd, Flush w/90 B crude, Max P 2800#, §  
 151 BLO/NT, § 165 B of 274 BL & AW w/NS, PB 5360, Pf 48/  
5318-30 (Mrw), 1000A, § 1d, § 2 BO & 8 BSW/4 hrs, 3000A,  
 § 1d & 1 2/3 BO (Gr 33 deg) & 13 BSW/11 hr, § 1 2/3 BO &  
 15 BSW/16 hrs - D & A 10-19-65 - COMPLETED

D&A

Data Inc

MISCEL DATA

GEOL Bill Jacques ELEV <sup>P-5</sup> 3081 DF SPUD DATE 9-25-65

FTG \_\_\_\_\_ 3072 GR DRLG COMP \_\_\_\_\_

SUPPT \_\_\_\_\_ FR by DATA 9-21-65

CSG 8" @1930 w/600 sx. 4" @5448 w/110 sx. COMP by " 10-28-65

LIBERAL ELECTRIC LOG TOPS

3083 KB

*Win 2716 +383*

Heebner 4058 (-975)

Toronto 4072 (-989)

Lansing 4152 (-1069)

"C" Zone 4400 (-1317)

"D" Zone 4578 (-1495)

Marmaton 4734 (-1651)

Pay Zone 4768 (-1685)

Morrow 5230 (-2147)

Lime 5314 (-2231) 9/25

"S-3" Sand 5380 (-2297) 3/10

Chester 5440 (-2357)

Ste. Gen 5514 (-2431)

TD 5550 D & A