

90319

MAP NO. _____ 1-26-61 ELEV. 3138 KB 3135 DF
 STATE Kansas COUNTY Grant SEC. 7 Twp 28 S Rge 38 W
 OPERATOR Pan American Petroleum Corporation LOC. C NE SW
 WELL NO. 1 FARM NAME R. P. Pinegar G U "B" * FT. FROM _____ LINE
 TOOL WILDCAT (PD 5900) FT. FROM _____ LINE
 FR. 12-14-60 SPUD 12-14-60 COMP. 1-23-61

CONT./GEOL.

COMPLETION RECORD

NAME PRODUCING INTERVAL FROM — TO PERF. W/HOLES TREATMENT RECORD
 a Council Grove 2864-2809 48 5500 gel wtr

b _____

c _____

d _____

a I. P. OIL/DIST. WTR 72/20 ga GAS 7775 M.C.F.P.D. CHK. 3" HRS. 24

b " " " " " "

c " " " " " "

d _____

D & A ()

SIP# 395 FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT 2845 TD 6000

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
<u>9-5/8"</u>	<u>715</u>	<u>450</u>			
<u>4 1/2"</u>	<u>2882</u>	<u>200</u>			

OPERATOR Pan Am Pet Corp WELL NO. 1 R. P. Pinegar G U "B" ELEV. 3138 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
* change farm name			Council Grove	2600	+538
from # 1 Pinegar to			Pennsylvanian	3169	
# 1 Pinegar Gas Unit "B"			Missouri	3786	
			Des Moines	4433	
			Morrow	5070	1932
			Chester	5402	2264
			Ste. Genevieve	5421	2243
			St. Louis	5574	2436
			Salem	5840	

Spud 12-14-60. 9-5/8" @ 715 w/450 sx.

TD 6000, Elogs to 6000.

WLT # 1 @ 5862, op 70 mins, rec 110 cc FtW, ISIP less than 50/30 mins, FSIP less than 50/30 mins.

WLT # 2 @ 2807, op 1 hr, rec 5250 cc FtW + 1.54 CFG, ISIP 400/5 mins, FSIP 400/20 mins.

WLT # 3 @ 4476, op 1 hr, rec 1010 cc FtW, ISIP 1185/15 mins, FSIP 1350/30 mins.

WLT # 4 @ 4078, op 1 hr, rec 6550 cc FtW, ISIP 1190/15 mins, FSIP 119/15 mins.

WLT #5 @ 5577, op 4 mins, rec 20,900 cc FtW, ISIP 1600/15 mins,
FSIP 1600/2 mins.

4½" @ 2882 w/200 sx. CO to 2845.

P 16/2807-09, 16/2764-66, frac 5,500 wtr X no sd./20 ball sealers

Flush w/3000 gal wtr. Max break down Pr 1800. Max trt pr 1600.

IP 72/20 g 7,775 MCF, SIP 395, Est del 3,300 MCF (against
80% of well head SIP) from Council Grove (2664-2809 O/A).

LIBERAL ELECTRIC LOG TOPS

3138 KB

Winfield 2376 (+762)

Council Grove 2616 (+522) ϕ g7,775 MCF

Heebner 3734 (-596)

Toronto 3760 (-622)

Lansing 3844 (-706)

Marmaton 4430 (-1294)

Morrow 5070 (-1932)

"S-3" 5336 (-2198) 0/48

Chester 5384 (-2246)

TD 6000