

90134

A-4-213

MAP NO.

K-79 ✓

3201 KB

ELEV 3199 DF 3188 EGL

STATE Kansas COUNTY Stanton SEC. 8 Twp 28 S Rge 39 WOPERATOR Pan American Petroleum Corporation LOC. NE SWWELL NO. 1 FARM NAME Glenn GU "B" FT. FROM _____ LINE _____L WILDCAT (PD 5800) FT. FROM _____ LINE _____FR. 4-4-61 SPUD. 4-5-61 COMP. 4-26-61CONT./GEOL. Herndon tools

COMPLETION RECORD

NAME PRODUCING INTERVAL FROM — TO PERF. W/HOLES TREATMENT RECORD

a					
b					
c					
d					

d I. P. OIL/DIST. _____ WTR. _____ GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. _____

b " " " " " "

c " " " " " "

d

D & A

D & A (1)

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT _____ TD 5850 5800

SIZE	DEPTH	CASING - CEMENT W/SAX.	SIZE	DEPTH	W/SAX.
<u>10-3/4"</u>	<u>693</u>	<u>600</u>			

OPERATOR Pan Am Pet CorpWELL NO. 1 Glenn GU "B"ELEV. 3201 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Council Grove	2554	+647
			Pennsylvanian	2992	
			Missouri	3792	
			Des Moines	4402	
			Morrow	5073	-1872
			Morrow Sand	5150-64	1949
			Morrow Sand	5354-66	2153
			Morrow Sand	5376-86	2175
			Ste Genevieve	5414	2213
			St Louis	5486	2285

Spud 4-5-61. 10-3/4" @ 693 w/600 sx. RTD 5850, logs.

WLT # 1 (Morr) @ 5161, op 1 hr, rec 70 cc wtr/NS, ISIP 0/15 mins, FSIP 0/15 mins.

WLT # 2 (St L) @ 5575, op 1 hr, rec 5800 cc wtr/NS, ISIP 1450/15 mins, FSIP 1510/20 mins.

WLT # 3 (Morr) @ 5385, op 1 hr, no rec, ISIP 0/15 mins, FSIP 0/30 mins.

WLT # 4 @ 5382, failed.

WLT # 5 @ 5383, failed.

WLT # 6 (Morr) @ 5229, op 61 mins, no rec, ISIP 0/15 mins, FSIP 0/30 mins.

WLT #7 @ 5034, op 1 hr, rec 13,600 cc wtr/NS, ISIP 1540/20 min
FSIP 1415/20 mins.

WLT #8 (CG) @ 2734, op 1 hr, rec 460 cc wtr/NS, ISIP 400/20
mins, FSIP 0/30 mins.

D & A.

LIBERAL ELECTRIC LOG TOPS

3201 KB

Winfield 2350 (+851)

Council Grove 2576 (+625) WLT wtr NS

Heebner 3714 (-513)

Toronto 3734 (-533)

Lansing 3814 (-613)

Mrmaton 4402 (-1201)

Morrow 5073 (-1872) T 337'; Tsd 36'

"S-2" Sand 5150 (-1949) 4/14; WLT 70 cc wtr, NS

"S-3" Sand 5354 (-2153) 10/22; WLT no rec.

Ste. Gen 5410 (-2209)

St. Louis 5498 (-2297)

TD 5800

D & A