


11-286W MAP NO. K-78 OWWO SEC. 8-28S-34W
 STATE Kans COUNTY Haskell LOC C NE NE
 OPER. R.W. Rine Drilling Co - Wichita, Kansas FT/FR _____ LINE _____
 WELL 1-B FARM Fletcher FT/FR _____ LINE _____
Eubank North Ext ELEV. _____ GR. 3086 DF _____ KB _____
 CONT. Burch Drlg. (CT) GEOL. _____
 CO. INT. _____
 F.R. 8-13-64 SPUD 8-14-60 COMP. 11-24-64
 TD. 5722 FM. St Gen PBTD. 5417
 COMP. RECORD
Chest ~~Mo sd~~ 5408-5412 16 1000A
Co P 40 BOPD & tr wtr, Gr 36 deg.
8" @780 w/350 sx. 5 1/2" @5482 w/100 sx.



Data Inc.

(Old DF Log) OLD INFO: (Was Russell McGuire #1
 Herr 2609 f 477 Fletcher)
 Kri 2637 f 449 DST #1 (Lans) 4133-98 (Str Pkr), Op 1 hr,
 Winf 2700 f 386 R 1080' SW, IFP 66#, FFP 400#, FSIP 979#/
 U/FR 2754 f 332 30"
 L/FR 2806 f 289 DST #2 (Mrw sd) 5331-60, Op 1 hr, R 20'
 CG 2942 f 144 VSGCM, ISIP 1375#/30", IFP 21#, FFP 42#,
 Hb 4030 - 944 FSIP 189#/30", RTD 5722, Log, 5 1/2" @5482
 Lans 4126 -1040 w/100 sx., Pf 28/5350-57, 32/5328-36,
 (ont Below) 200 MA, \$ 11 BO/10 hrs, Frac 5 x 5, \$ 41

→ See Other ticket for C Soil Tops ←

Marm 4722 -1636 BO/9 hrs-NW, SI, P 34 BOPD & tr wtr
 Chero 4859 -1773 NEW INFO: Prod declined - old well plugg-
 Mrw sh 5172 -2086 ed, MICT 8-16-64, CO 5417 PBTD, Sho G&O,
 Mrw sd 5330 -2244 \$ 3/4 BFPH/NT, \$ 1 1/4 BFPH (App 10% wtr),
 B/Mrw sd 5336 -2250 Log to 5405, set plg @5432 between old
 Mrw sd 5350 -2264 pfs, \$ 5328-36, (Old Mrw pfs), \$ 1 BOPH-
 B/Mrw sd 5356 -2270 NW, CO 5417, Cut slot @5352-54, Tbg w/
 Chest 5368 -2282 pkr @5274, 500 MCA, \$ ld, no new oil,
 Chest sd 5402 -2316 2000A (15%) & 500# rock salt, 2000A (15%)
 St G 5484 -2398 & 1000# rock salt, Tbg w/pkr @5280, treat
 St L 5513 -2427 w/15 BO & 800# moth balls, treat w/25 BO
 LTD NA & 1400# moth balls, Pull T&P, \$ (csg)
 (Old DF Spl) total 429 B ld (-100 BL), Frac (Csg) 8000
 4034 gal oil x 8000# sd x 2000# plugging agent
 or 4050 x 4000# plugging agent x 12,000 gal oil
 Lans 4133 x 12,000# sd, Rec 542 B of 1000 B ld,
 RTD 5722 Lost 350 B of ld, CO 5417, PF 16/5408-12
 (Rine Tops-DF) (Chest), \$ dry, 1000A, \$ ld, \$ 11 hrs,
 Chest sd 5402 -2316 then \$ 5BOPH (new) (Grindout 4% wtr)/8
 B/Chest sd 5417 -2331 hrs & Stab (Gr NA), P 40 to 50 BOPD & 1%
 St G 5446 -2360 wtr, Rec all ld, POP, State Pot Above,
 (Old Mrw perfs 5328-36 & 5350-57 - open) - COMPLETED

Tops on Maguire, Fletcher.
Ticket