

1-116W

MAP NO.

K-78

SEC. 8-28S-34W

STATE Kansas

COUNTY Haskell

LOC. C SW NE

OPER. R. W. Rine Drilling Co. - Wichita, Kansas

FT/FR

LINE

WELL #1 FARM Fletcher "C"

FT/FR

LINE

Eubank North (Mrw oil)

ELEV. 3077

GR. 3084

DF 3087

KB

CONT. Co. tools

GEOL. Paul Harper

INT. 5500' Oil Test

F.R. 11-13-64

SPUD

11-16-64

COMP.

1-7-65

TD. 5500

FM.

Ste Cen


PBTD.

5322

Morr 5252-5309 1/2 6 Nat

State Pot: P 148 BOPD / tr W (Gr 36.9 deg)

8-5/8" @1926' w/750 Sx. 5" @5461' w/300 Sx.



Data Inc.

CSO
W/m 371

"D"

(KB Log Tops:)

Hb 4056 - 969
 Tor 4072 - 985
 Lans 4155 - 1068
 KC-A 4570 - 1483
 KC-B 4628 - 1541
 Marm lm 4720 - 1633
 Mrw sh 5210 - 2123
 Mrw lm 5250 - 2163
 Mrw sd 5305 - 2218

DST #1 (Mrw) 5250-5300, Op 15", GB, SI/60", TSTM, Op 60", SI/60", R 1375' flU (975' oil, 400' MGO) (Gr 38 deg @ 68 deg) ISIP 1269#/60", IFP 201#, FFP 432#, FSIP 1223#/60",
DST #2 (Mrw) 5313-5400, Op 15", SI/60", R 150' SOCM, ISIP 339#/60", IFP 77#, FFP 108#, FSIP 185#/60", RTD 5500, Log, 5 1/2" @5461' w/300 Sx., w/DV tool @ 3011 w/150 Sx., CO 5430, Sj Log, to 5418 1/2, LW GRN,

Ste G 5450 - 2363
 LTD NA
 (KB Sp1 Tops:)
 Anh 1876 /1211
 Hb 4058
 Tor 4057
 Lans 4158
 Marm 4717
 Cher 4870 - 1783
 Atoka 4989 - 1902
 Mrw sh 5199
 Mrw lm 5261
 RTD 5500 - 2413

Log, 1/5374, 1/5371, 1/5356 1/2, 1/5351 1/2, 1/5330 1/2 (Morr) SS OCM at 5330 1/2, 2500 MCA (Load 16 BAW / 140 Blo) \$ & rec 1d, \$ 70 BO/2 hrs, 15/5370-75, 3/5356-57, 6/5351-53 6/5329-31 (Morr) \$ 8-10 BOPH (1.4% BS) = 50 (Gr 35.5 deg) PB 5322, Pf 1/5307 1/2-09 1/2, 1/5293 1/2-96, 1/5288-91, 1/5282-84, 1/5268-70, 1/5252-55 (Mrw), \$ from 3000', \$ 8 1/2 BOPH/NT, \$ total 218 BO/31 hrs, Gr 35.5 deg, T&R, POP, P 120 BOPD (Mrw lm Pfs only) State Pot: (8 hrs rate) P 148 & tr wtr, Gr 36.9 deg, Morr 5252-5309 1/2 - COMPLETED 1-6-65

LIBERAL ELECTRIC LOG TOPS

3087 KB

Winfield 2720 (+367)

Heebner 4056 (-969)

Toronto 4072 (-985)

Lansing 4158 (-1069)

"C" Zone 4392 (-1305)

"D" Zone 4570 (-1483)

Marmaton 4720 (-1633)

Morrow 5210 (-2123)

Lime 5250 (-2163) ϕ pmp 148 BOPD

"S-3" Zone 5348 (-2261) 9/20; pmp 8-10 BOPH

Chester 5420 (-2333)

Ste. Gen 5492 (-2405)

TD 5500

Mem Page 7 4744-1657