

26-29-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- Natural Gas & Oil Co.,
Farm- Larrison No. 2

SEC. 26 T. 29 R. 13W
SW NE SW

Total Depth. 4665'
Comm. 6-1-57 Comp. 6-20-57
Shot or Treated.
Contractor. Sierra Petroleum
Issued. 2-15-58

County Pratt
KANSAS



Elevation. 1861' KB.

Production. 7,866,000 CFG &
20 BOPD.

CASING:

8 5/8" @ 341' w/275 sks. cem.,
5 1/2" @ 4633 1/2' w/150 sks. cem.,

Figures indicate Bottom of Formations.

sand	200
red bed	748
Anhydrite	755
red bed & shale	875
shale & salt	1175
shale & shells	1850
lime & shale	2135
lime	2275
lime & shale	2510
lime	2555
shale & lime	3125
lime & shale	3798
lime	4315
Conglomerate	4344
lime & shale	4390
lime	4433
Viola lime	4526
Simpson	4627
Arbuckle	4634
lime ?	4665
Total Depth	

TOPS: SCOUT:

Anhydrite	748
Heebner	3670
Douglas	3738
Brown Lime	3850
Kansas City	3865
Lansing	3866
Conglomerate	4306
Kinderhook	4360
Viola	4406
Simpson Shale	4524
Simpson	4526
Simpson Sand	4538
Arbuckle	4627