

26-29-13W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas


Company- NATURAL GAS & OIL
Farm- Larrison No. 3

SEC. 26 T. 29S R. 13W
C S/2 SW SW

Total Depth. 4572'
Comm. 12-1-59 Comp. 12-11-59
Shot or Treated.
Contractor. S & S Drilling
Issued. 2-13-60

County Pratt

KANSAS



Elevation. 1826 GL

Production. 6,978,000 CFG

Figures indicate Bottom of Formations.

sand	185
red bed, shale	891
shale & sholls	1300
salt	1575
shale, lime streaks	1885
lime & shale	2390
shale & lime	2710
lime & shale	3530
lime	3620
lime & shale	3785
lime	4175
lime & shale	4415
lime	4453
lime & shale	4511
Simpson sand	4572
Total Depth	

TOPS:	
Heebner	3638
Brown lime	3819
Lansing	3834
Base Kansas City	4197
Conglomerate	4279
Kinderhook	4299
Viola	4374
Simpson	4490
Simpson sand	4506

Perf. 4376-88 w/50 bullets. Acidized
w/500 gal. mud acid.